

ADDENDUM NO. 2

**SUDBURY ROAD LANDFILL REMEDIAL ACTION
CITY OF WALLA WALLA**

Addendum No.2 to the Plans, Specifications, and Contract Documents as prepared by **J-U-B ENGINEERS, Inc.**, is hereby submitted via facsimile or email for use in bid preparation and submittal.

NOTE: Subsoil Type S2 Backfill for the LFG extraction wells shall be imported gravel backfill conforming to WSDOT Standard Specification 9-03.12(3). All other locations where S2 soil is stated (besides the LFG extraction wells) shall conform to the requirements of Section 02205 3.1C.

NOTE: Monday, February 15 is an observed holiday. J-U-B office closes at 11:30 am on Fridays. No additional questions will be answered after 11:30 am on Friday, February 12.

The following changes, additions, and/or deletions are hereby made a part of **Sudbury Road Landfill Remedial Action**, dated January 2016, as fully and completely as if the same were entirely set forth in the Plans, Specifications, and Contract Documents. Changes and additions are noted in ***bold italics***, and deletions are noted in ~~strikethrough~~.

VOLUME I – BIDDING FORMS, AGREEMENT FORMS, AND TECHNICAL SPECIFICATIONS

SECTION 15100, Landfill Gas Wells

Modify sub-section 2.2 to read:

~~Subsoil Type S2 backfill and Drainage Aggregate~~ shall conform to materials specifications as identified in Section 02205 – Soil Materials and Aggregates. ***Subsoil Type S2 for the LFG extraction wells shall be imported gravel backfill meeting WSDOT Standard Specification 9-03.12(3).***

Submitted by:

J-U-B ENGINEERS, Inc.



Benjamin Haws, P.E.
Project Engineer

DATE: 2-12-2016