

CODE COMPLIANCE

ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

2021 INTERNATIONAL BUILDING CODE WITH LOCAL AMENDMENTS
 2018 NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 1
 2018 INTERNATIONAL ENERGY CONSERVATION CODE
 2021 WASHINGTON STATE ENERGY CODE
 2021 INTERNATIONAL FIRE CODE WITH AMENDMENTS

PROPERTY LEGAL DESCRIPTION:
 SEE SCHEDULE "C" OF TITLE REPORT

SITE NUMBER: WL4557
SITE NAME: WALLA WALLA MILL CREEK
SITE TYPE: MONOPINE / WIC
ADDRESS: 928 STURM AVE
 WALLA WALLA, WA 99362
MAP AND TAX LOT: 360728140121



NEW BUILD LTE ONLY 1C: MRWOR035937
 LTE 3C: MRWOR050243
 LTE 2C: MRWOR050240
 LTE 5C: MRWOR050241
 LTE 4C: MRWOR050242
 USID: 291228
 FA CODE: 14641286

PREPARED FOR

NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
 19801 SW 72ND AVE., STE. 200
 TUALATIN, OR 97062

Vendor:

23 MAUCHLY #110
 IRVINE, CA 92618
 J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA MILL CREEK
 928 STURM AVE
 WALLA WALLA, WA 99362
 PARCEL ID:
 47662 & 47722

PROJECT TEAM

APPLICANT / LESSEE: NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
 19801 SW 72ND AVE., STE. 200
 TUALATIN, OR 97062


PROJECT MANAGER: J5 INFRASTRUCTURE PARTNERS
 CONTACT: SARA MITCHELL
 EMAIL: samitchell@j5ip.com
 PH: (971) 281-1422

CONSTRUCTION MANAGER: CONTACT: RANDY MORRISON
 EMAIL: rx191c@att.com
 PH: (425) 492-6590

SITE ACQUISITION: J5 INFRASTRUCTURE PARTNERS
 CONTACT: KELLY LEA
 EMAIL: klea@j5ip.com
 PH: (503) 380-2717

A&E MANAGER: J5 INFRASTRUCTURE PARTNERS
 CONTACT: JARRETT ELLINGTON
 EMAIL: jellington@j5ip.com
 PH: (706) 294-1479

ZONING: J5 INFRASTRUCTURE PARTNERS
 CONTACT: PHILLIP KITZES
 EMAIL: pkitzes@j5ip.com
 PH: (206) 227-7445



PROJECT DESCRIPTION

PROPOSED SITE BUILD OF AN UNMANNED TELECOMMUNICATIONS FACILITY, CONSISTING OF THE FOLLOWING:

TOWER/ANTENNA SOW:

- INSTALLATION OF (1) AT&T 6'-0" TALL LIGHTNING ROD
- INSTALLATION OF (1) AT&T 59'-0" TALL MONOPINE
- INSTALLATION OF (6) AT&T PANEL ANTENNAS
- INSTALLATION OF (9) AT&T REMOTE RADIO UNITS (RRU'S)
- INSTALLATION OF (6) AT&T RRH MOUNT KITS
- INSTALLATION OF (1) AT&T DC-9 SURGE SUPPRESSOR
- INSTALLATION OF (3) AT&T V-FRAME ANTENNA MOUNTS

EQUIPMENT SOW:

- INSTALLATION OF AN AT&T 30'-0" X 50'-0" (1,500 SQ. FT.) TELECOMMUNICATION COMPOUND LEASE AREA
- INSTALLATION OF AT&T 28'-0" X 48'-0", 6'-0" HIGH CHAIN LINK FENCING W/ PRIVACY SLATS
- INSTALLATION OF (1) AT&T WALK-IN CABINET (WIC) ON CONCRETE PAD
- INSTALLATION OF (1) AT&T 20KW DC DIESEL BACK-UP GENERATOR ON CONCRETE PAD
- INSTALLATION OF (1) AT&T 200A AC POWER PANEL
- INSTALLATION OF (1) AT&T EMERSON POWER PLANT RACK W/ (12) BATTERIES
- INSTALLATION OF (2) AT&T HYBRID RACKS
- INSTALLATION OF (1) AT&T FLEX 12 CABINET
- INSTALLATION OF (1) AT&T H-FRAME W/ UTILITY EQUIPMENT
- INSTALLATION OF (1) AT&T CABLE BRIDGE
- INSTALLATION OF (3) AT&T POWER & (1) FIBER CABLE TRUNKS
- INSTALLATION OF (1) AT&T DC 12 SURGE SUPPRESSORS BOXES
- INSTALLATION OF (10) AT&T RECTIFIERS
- INSTALLATION OF (1) AT&T BASEBAND UNIT
- INSTALLATION OF (1) AT&T GPS ANTENNA
- INSTALLATION OF (1) AT&T FIBER VAULT
- INSTALLATION OF (21) EVERGREEN TREES WITH A 10' TO 12' MAX. MATURE HEIGHT
- INSTALLATION OF (12) EVERGREEN TREES WITH A 30' TO 40' MAX. MATURE HEIGHT
- INSTALLATION OF (1) AT&T 8'-0" TALL, 17'-0" X 19'-0" NOISE BARRIER

PROJECT AREA:

- 32'-0" X 50'-0" (1,600 SQ. FT.) LEASE AREA

DRAWN BY: RC
 CHECKED BY: EVR

0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

SITE INFORMATION

PROPERTY OWNER: FIRST CHURCH OF GOD
 1010 STURM AVE.
 WALLA WALLA, WA 99362

JURISDICTION: WALLA WALLA COUNTY
EXPOSURE CATEGORY: C

GROUND SNOW LOAD	WIND SPEED	SEISMIC DESIGN CATEGORY	WEATHERING	FROST LINE DEPTH	TERMITES
30 LBS./FT. ²	110 MPH ULTIMATE WIND SPEED FOR RESIDENTIAL/COMMERCIAL	D	SEVERE	2'-0"	SLIGHT TO MODERATE
DECAY	WINTER DESIGN TEMP	ICE SHIELD UNDERLAY	FLOOD HAZARD	AIR FREEZE INDEX	MEAN ANNUAL TEMP
NONE TO SLIGHT	10°	YES	2003 1992 FIRM	1000	50.2°

MAP AND TAX LOT: 360728140121
ZONING: RESIDENTIAL NEIGHBORHOOD
LATITUDE (NAD 83): 46.05910°
LONGITUDE (NAD 83): -118.30927°
IMPERVIOUS SURFACE SF: ±200 SQ. FT.
BASE OF EXISTING STRUCTURE: ±0'-0" (±1033.50' AMSL)
TOP OF EXISTING STRUCTURE: ±100'-0" (±1133.50' AMSL)
TOP OF STRUCTURE W/ HIGHEST APPURTENANCE: ±105'-0" (±1138.50' AMSL)

ACCESSIBILITY REQUIREMENTS: FACILITY IS AN UNMANNED EQUIPMENT SPACE NOT INTENDED FOR HUMAN HABITATION AND ONLY FREQUENTLY VISITED BY MAINTENANCE PERSONAL. ACCESSIBILITY IS NOT REQUIRED PER IBC 2018, SECTION 1103.2.9 (EQUIPMENT SPACES)
TOWER OWNER: AT&T
POWER AGENCY: PACIFIC POWER
TELEPHONE AGENCY: TBD
RFDS VERSION: FINAL/1.0
DATE UPDATED: 7/30/2020

GENERAL CONTRACTOR NOTES

DO NOT SCALE DRAWINGS

THESE PLANS ARE FORMATTED TO BE FULL SIZE AT 24" X 36". CONTRACTORS SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR MATERIAL ORDERS OR BE RESPONSIBLE FOR THE SAME.

GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE; NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

STATEMENTS

STRUCTURAL ANALYSIS IS NOT WITHIN THE SCOPE OF WORK CONTAINED IN THIS DRAWINGS SET. FOR ANALYSIS OF EXISTING AND/OR PROPOSED COMPONENTS, REFER TO STRUCTURAL ANALYSIS PROVIDED UNDER SEPARATE COVER.

ANTENNA MOUNT ANALYSIS IS NOT WITHIN THE SCOPE OF WORK CONTAINED IN THIS DRAWING SET. FOR ANALYSIS OF MOUNT TO SUPPORT EXISTING AND/OR PROPOSED COMPONENTS, REFER TO ANTENNA MOUNT STRUCTURAL ANALYSIS PROVIDED UNDER SEPARATE COVER.

DRIVING DIRECTIONS

DIRECTIONS FROM AT&T OFFICE LOCATED AT 19801 SW 72ND AVE, TUALATIN, OR 97062:

1. HEAD EAST TOWARD SW 72ND AVE (30 FT)
2. TURN LEFT TOWARD SW 72ND AVE (128 FT)
3. TURN RIGHT ONTO SW 72ND AVE (489 FT)
4. TURN LEFT AT THE 1ST CROSS STREET ONTO SW SAGERT ST (0.4 MI)
5. TURN LEFT ONTO SW 65TH AVE (0.5 MI)
6. CONTINUE STRAIGHT PAST 7-ELEVEN ONTO SW NYBERG ST (0.3 MI)
7. MERGE ONTO I-5 N (9.9 MI)
8. KEEP RIGHT TO STAY ON I-5 N (1.1 MI)
9. USE THE RIGHT 2 LANES TO TAKE EXIT 300 FOR I-84 E/US-30 E TOWARD PORTLAND AIRPORT/THE DALLES (1.1 MI)
10. CONTINUE ONTO I-84 E/US-30 E (176 MI)
11. TAKE EXIT 179 FOR I-82 W TOWARD HERMISTON/UMATILLA (0.8 MI)
12. CONTINUE ONTO I-82 W (9.1 MI)
13. TAKE EXIT 1 FOR US-395 S/US-730 S TOWARD UMATILLA IRRIGON (0.3 MI)
14. TURN RIGHT ONTO US-395 S/US-730 S TOWARD UMATILLA IRRIGON (0.3 MI)
15. CONTINUE TO FOLLOW US-730 E (25.2 MI)
16. MERGE ONTO US-12 E (31.0 MI)
17. TURN RIGHT ONTO WILBUR AVE (1.4 MI)
18. TURN RIGHT ONTO PLEASANT ST (0.1 MI)
19. TURN LEFT ONTO STURM AVE AND SITE WILL BE ON THE RIGHT (0.2 MI)



SHEET INDEX

REV	DATE	DESCRIPTION	REV.
T-1		TITLE SHEET	3
GN-1		GENERAL NOTES	3
GN-2		GENERAL NOTES	3
GN-3		SITE SIGNAGE	3
GN-4		MATERIAL SAFETY DATA SHEET & LEAD ACID BATTERY - 1	3
GN-5		MATERIAL SAFETY DATA SHEET & LEAD ACID BATTERY - 2	3
SU-1		SITE SURVEY	-
1A		1A CERTIFICATION	-
A-1		SITE PLAN	3
A-1.1		AERIAL SITE PLAN	3
A-2		ENLARGED SITE PLAN & COMPOUND PLAN	3
A-3		ANTENNA PLAN & SCHEDULE & EQUIPMENT PLAN	3
A-4		NORTH ELEVATIONS	3
A-5		EAST ELEVATIONS	3
A-6		SOUTH ELEVATIONS	3
A-7		WEST ELEVATIONS	3
L-1		CONCEPTUAL LANDSCAPE PLAN	3
D-1		DETAILS	3
D-2		DETAILS	3
D-3		DETAILS	3
D-4		GENERATOR DETAILS	3
D-5		WALK-IN CABINET (WIC) DETAILS	3
D-6		ANTENNA MOUNT DETAILS	3
E-1		UTILITY PLAN	3
E-2		ELECTRICAL PANEL SCHEDULE & SLDG	3
G-1		GROUNDING NOTES	3
G-2		GROUNDING PLANS	3
G-3		GROUNDING DETAILS	3

Licenser:

Sheet Title:
TITLE SHEET

Sheet Number:
T-1

SITE WORK GENERAL NOTES:

1. THE SUBCONTRACTOR SHALL CONTRACT UTILITY LOCATING SERVICES PRIOR TO THE START OF CONSTRUCTION.
2. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC, AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE SUBCONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES, SUBCONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A.) FALL PROTECTION B.) CONFINED SPACE C.) ELECTRICAL SAFETY D.) TRENCHING AND EXCAVATION.
3. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND PROJECT SPECIFICATIONS.
4. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES, AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
5. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC, AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED, OR OTHERWISE DISCONNECTED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF CONTRACTOR, OWNER, AND/OR LOCAL UTILITIES.
6. THE SUBCONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE.
7. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE BTS EQUIPMENT AND TOWER AREAS.
8. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW, OR ICE SHALL BE PLACED IN ANY FILL OR EMBANKMENT.
9. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
10. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT, OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE PROJECT SPECIFICATIONS.
11. SUBCONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
12. NOTICE TO PROCEED - NO WORK TO COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF A PURCHASE ORDER.
13. ALL CONSTRUCTION MEANS AND METHODS: INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN AND SHALL ADHERE TO ANSITIA-1019 (LATEST EDITION) INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION.

CONCRETE AND REINFORCING STEEL NOTES:

1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185, AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
2. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 2,500 PSI AT 28 DAYS, UNLESS NOTED OTHERWISE. SLAB FOUNDATION DESIGN ASSUMING ALLOWABLE SOIL BEARING PRESSURE OF 2000 PSF.
3. REINFORCING STEEL SHALL CONFORM TO ASTM A615, GRADE 60, DEFORMED UNLESS NOTED OTHERWISE. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A185 WELDED STEEL WIRE FABRIC UNLESS NOTED OTHERWISE. SPLICES SHALL BE CLASS "B" AND ALL HOOKS SHALL BE STANDARD. UNO.
4. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS.
 - 4.1. CONCRETE CAST AGAINST EARTH: 3" MIN.
 - 4.2. CONCRETE EXPOSED TO WEATHER:
 - 4.2.1. #6 AND LARGER - 2" MIN.
 - 4.2.2. #5 AND SMALLER & WWF. - 1 1/2" MIN.
 - 4.3. CONCRETE NOT EXPOSED TO WEATHER OR NOT CAST AGAINST THE GROUND:
 - 4.3.1. SLAB AND WALLS 3/4" MIN.
 - 4.3.2. BEAMS AND COLUMNS 1 1/2" MIN.
5. A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4

GENERAL NOTES:

1. FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:

CONTRACTOR -	J5 INFRASTRUCTURE PARTNERS
SUBCONTRACTOR -	GENERAL CONTRACTOR (CONSTRUCTION)
CARRIER -	AT&T
OEM -	ORIGINAL EQUIPMENT MANUFACTURER
2. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING SUBCONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE THEMSELVES, WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF THE CONTRACTOR AND AT&T
3. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES. SUBCONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS, AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
4. DRAWINGS PROVIDED HERE ARE NOT TO SCALE AND ARE INTENDED TO SHOW OUTLINE ONLY.
5. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
6. 'KITTING LIST' SUPPLIED WITH THE BID PACKAGE IDENTIFIES ITEMS THAT WILL BE SUPPLIED BY CONTRACTOR. ITEMS NOT INCLUDED IN THE BILL OF MATERIALS AND KITTING LIST SHALL BE SUPPLIED BY THE SUBCONTRACTOR.
7. THE SUBCONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
8. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE SUBCONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CONTRACTOR AND AT&T PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
9. SUBCONTRACTOR SHALL DETERMINE ACTUAL ROUTING OF CONDUIT, POWER AND T1 CABLES, GROUNDING CABLES AS SHOWN ON THE POWER, GROUNDING AND TELCO PLAN DRAWINGS.
10. THE SUBCONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT THE SUBCONTRACTOR'S EXPENSE; TO THE SATISFACTION OF THE OWNER.
11. SUBCONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
12. SUBCONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION, TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.

PREPARED FOR



NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
19801 SW 72ND AVE., STE. 200
TUALATIN, OR 97062

Vendor:



23 MAUCHLY #110
IRVINE, CA 92618

J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
928 STURM AVE
WALLA WALLA, WA 99362
PARCEL ID:
47662 & 47722

DRAWN BY: RC

CHECKED BY: EVR

0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV	DATE	DESCRIPTION
-----	------	-------------


Licenser:

Sheet Title:

GENERAL NOTES

Sheet Number:

GN-2



This Site Operated by:
AT&T MOBILITY
 AT&T MOBILITY 16221 NE 72ND WAY, REDMOND WA, 98052
 IN CASE OF FIRE AND THE NEED FOR SHUTDOWN
 TO DEACTIVATE ANTENNAS CALL THE
 FOLLOWING NUMBER:
 For 24 Hour Emergency Contact and Access Please Call:
 (800) 638-2822

Reference Site#: WL4557
 Site Address: 928 STURM AVE WALLA WALLA, WA 99362

10 FENCED COMPOUND SIGNAGE
N.T.S.



DANGER
NO TRESPASSING

9 FENCED COMPOUND SIGNAGE
N.T.S.



NOTICE
AUTHORIZED PERSONNEL ONLY


8 DOOR / EQUIPMENT SIGN
N.T.S.



DANGER
DIESEL FUEL
NO SMOKING
NO OPEN FLAMES


DANGER
LEAD ACID BATTERIES
CORROSIVE LIQUIDS (ELECTROLYTE)
ENERGIZED ELECTRICAL CIRCUITS
NO SMOKING

7 NFPA HAZARD SIGN - TYPICAL
N.T.S.




INFORMATION
 Federal Communications Communication
 Tower Registration Number
1 2 3 4 5 6 7
 Posted in accordance with federal Communications
 Commission rules and antenna tower registration
 47CFR 17.4(g).

6 FCC ASR SIGNAGE
N.T.S.




Property of AT&T
Authorized Personnel Only
 No Trespassing
 Violators will be Prosecuted
 In case of emergency, or prior to performing
 maintenance on this site, call _____
 and reference cell site number _____

5 GATE SIGNAGE
N.T.S.




Property of AT&T
Authorized Personnel Only
 In case of emergency, or prior to performing
 maintenance on this site, call _____
 and reference cell site number _____

4 SHELTER / CABINET DOORS SIGNAGE
N.T.S.




INFORMATION
 AT&T MOBILITY OPERATES TELECOMMUNICATION ANTENNAS AT THIS
 LOCATION. REMAIN AT LEAST 3 FEET AWAY FROM ANY ANTENNA AND OBEY
 ALL POSTED SIGNS.
 CONTACT THE OWNER(S) OF THE ANTENNA(S) BEFORE WORKING CLOSER
 THAN 3 FEET FROM THE ANTENNA(S).
 CONTACT AT&T MOBILITY AT 800-638-2822 PRIOR TO PERFORMING ANY
 MAINTENANCE OR REPAIRS NEAR AT&T MOBILITY ANTENNAS.
 THIS IS SITE # _____
 CONTACT THE MANAGEMENT OFFICE IF THIS DOOR/HATCH/GATE
 IS FOUND UNLOCKED.

A INFORMATION SIGN 1-1
SCALE: 1/2" = 1'




INFORMATION
 ACTIVE ANTENNAS ARE MOUNTED
 ON THE OUTSIDE FACE OF THIS BUILDING
 INFORMATION SIGN 1-2
 ON THIS STRUCTURE
 STAY BACK A MINIMUM OF 3 FEET
 FROM THESE ANTENNAS
 CONTACT AT&T MOBILITY AT 800-638-2822 &
 FOLLOW THEIR INSTRUCTIONS PRIOR TO
 PERFORMING ANY MAINTENANCE OR
 REPAIRS CLOSER THAN 3 FEET FROM THE
 ANTENNAS.
 THIS IS AT&T MOBILITY SITE _____

B INFORMATION SIGN 1-2
SCALE: 3/4" = 1'



INFORMATION
 SCALE: 1/4" = 1'

C INFORMATION SIGN 1-3
SCALE: 1/4" = 1'



INFORMATION
 SCALE: 3/16" = 1'

D INFORMATION SIGN 1-4
SCALE: 3/16" = 1'

1. CONTRACTOR SHALL INSTALL ALL INFORMATION SIGNAGE IN ACCORDANCE w/ AT&T WIRELESS DOCUMENT #03-0074, RF EXPOSURE POLICY AND RF SAFETY COMPLIANCE PROGRAM, LATEST EDITION.

2. FABRICATION:

*SIGN 1-1: ENTRANCE DOOR, SEE DETAIL 1A, THIS SHEET

SIGN 1 IS TO BE MADE ON THE 50 MIL ALUMINUM SHEETING (SIZE 8 INCHES BY 12 INCHES) w/ FOUR (4) 1/4 INCH MOUNTING HOLES, ONE EACH CORNER OF THE SIGN FOR MOUNTING w/ HARDWARE w/ TIE WRAPS. THE MAIN BACKGROUND COLOR IS TO BE WHITE FRONT & BACK w/ BLACK LETTERING.


THE INFORMATION BAND SHALL BE 1.2 INCH SOLID GREEN BAND w/ 0.5 INCH HIGH BLACK LETTERING. THE BODY TEXT SHALL BE IN BLACK LETTERING w/ 0.2 INCH HIGH LETTERS. THE REF LINE SHALL BE IN 1/8 INCH LETTERS.

THE PLACEMENT OF TEXT SHALL BE DONE IN A MANNER THAT WILL PERMIT EASY READING FROM A DISTANCE OF APPROXIMATELY 6 FEET IN FRONT OF THE SIGN.

3 INFORMATION SIGNAGE
N.T.S.

NOTE:

- CONTRACTOR SHALL INSTALL ALL INFORMATION SIGNAGE IN ACCORDANCE w/ AT&T WIRELESS DOCUMENT #03-0074, RF EXPOSURE POLICY AND RF SAFETY COMPLIANCE PROGRAM, LATEST EDITION.
- CONTRACTOR SHALL CONTACT AT&T R-RFSC FOR INFORMATION ON MPE LEVELS AND INSTRUCTIONS ON LEVEL AND LOCATION OF SIGNAGE



CAUTION

On this tower:
 Radio frequency (RF) fields near some antennas may exceed the FCC Occupational Exposure Limits.
 Contact AT&T at 800-638-2822, option 9 and 3, and follow their instructions prior to performing maintenance or repairs beyond this point.
 Personnel climbing this tower should be trained for working in RF environments and use a personal RF monitor if working near active antennas.
 Caution Sign #CADIT-AL-05.7 This is AT&T site 291228

2 CAUTION SIGN
N.T.S.

ALL PAINT WILL BE BAKED w/ ENAMEL w/ UV PROTECTIVE COATING OVER THE FACE OF THE SIGN.

*SIGN 1-2: POLE, SEE DETAIL 1B, THIS SHEET

SIGN 2 MUST BE A NON METALLIC LABEL w/ AN ADHESIVE BACKING. THE LABEL SHALL BE MADE USING VINYL OR SIMILAR WEATHERPROOF MATERIAL. THE LABEL SHALL BE APPROXIMATELY 5X7 INCHES w/ A WHITE BACKGROUND AND BLACK LETTERING. THE GREEN BAND SHALL BE 1.375 INCH IN HEIGHT & THE LETTERING SHALL BE BLACK w/ 0.75 INCH HIGH LETTERS. THE TEXT LETTERING SHALL BE BLACK w/ 1/8 INCH HIGH LETTERS. UV PROTECTION SHALL BE PLACED OVER THE FRONT OF THE LABEL.

*SIGN 1-3: BACK OF ANTENNAS, SEE DETAIL 1C & 3, THIS SHEET

*SIGN 3 IS A 1 INCH X 2 INCH PANEL THAT CAN BE APPLIED TO THE BACK OR SIDE OF AN ANTENNA TO IDENTIFY IT AS AN AT&T ANTENNA.

*SIGN 1-4: SIDE OF ANTENNAS, SEE DETAIL 1D & 3, THIS SHEET

SIGN 4 IS MADE FROM TRANSPARENT MATERIAL 1-1/2 INCHES WIDE & 24 INCHES LONG. THE LETTERING IS TO BE BLACK w/ 1/8 INCH LETTERING IN A VERTICAL COLUMN. THE SPACING BETWEEN WORDS MUST BE SUCH THAT IT IS EASILY READ & FILLS THE LENGTH OF THE SIGN.

SIGNAGE AND STRIPING INFORMATION

- THE FOLLOWING INFORMATION IS A GUIDELINE w/ RESPECT TO PREVAILING STANDARDS LIMITING HUMAN EXPOSURE TO RADIO FREQUENCY ENERGY AND SHOULD BE USED AS SUCH. IF THE SITE'S EMF REPORT OR ANY LOCAL, STATE OR FEDERAL GUIDELINES OR REGULATIONS SHOULD BE IN CONFLICT w/ ANY PART OF THESE NOTES OR PLANS, THE MORE RESTRICTIVE GUIDELINE OR REGULATION SHALL BE FOLLOWED AND OVERRIDE THE LESSER.
- THE PUBLIC LIMIT OF RF EXPOSURE ALLOWED BY AT&T IS 1mWcm*2 AND THE OCCUPATIONAL LIMIT OF RF EXPOSURE ALLOWED BY AT&T IS 5mWcm*2
- IF THE BOTTOM OF THE ANTENNA IS MOUNTED (8) EIGHT FEET ABOVE THE GROUND OR WORKING PLATFORM LINE OF THE PERSONAL COMMUNICATION SYSTEM (PCS) AND DOES NOT EXCEED THE PUBLIC LIMIT OF RF EXPOSURE LIMIT THEN NO STRIPING OR BARRICADES SHOULD BE NEEDED.
- IF THE PUBLIC LIMIT OF RF EXPOSURE ON THE SITE IS EXCEEDED AND THE AREA IS PUBLICLY ACCESSIBLE (e.g. ROOF ACCESS DOOR THAT CANNOT BE LOCKED, OR FIRE EGRESS) THEN BOTH BARRICADES AND STRIPING SHALL BE PLACED AROUND THE ANTENNAS. THE EXACT EXTENT OF THE BARRICADES AND STRIPING SHALL BE DETERMINED BY THE EMF REPORT FOR THE SITE DONE BEFORE OR SHORTLY AFTER COMPLETION OF SITE CONSTRUCTION. USE THE PLANS AS A GUIDELINE FOR PLACEMENT OF SUCH BARRICADES AND STRIPING.
- IF THE PUBLIC LIMIT OF RF EXPOSURE ON THE SITE IS EXCEEDED AND THE AREA IS PUBLICLY ACCESSIBLE (e.g. ROOF ACCESS DOOR THAT CANNOT BE LOCKED, OR FIRE EGRESS) THEN BOTH BARRICADES AND STRIPING SHALL BE PLACED AROUND THE ANTENNAS. THE EXACT EXTENT OF THE BARRICADES & STRIPING SHALL BE DETERMINED BY THE EMF REPORT FOR THE SITE DONE BEFORE OR SHORTLY AFTER COMPLETION OF SITE CONSTRUCTION. USE THE PLANS AS A GUIDELINE FOR PLACEMENT OF SUCH BARRICADES AND STRIPING.
- ALL TRANSMIT ANTENNAS REQUIRE A THREE LANGUAGE WARNING SIGN WRITTEN IN ENGLISH, SPANISH, AND CHINESE. THIS SIGN SHALL BE PROVIDED TO THE CONTRACTOR Y THE AT&T CONSTRUCTION PROJECT MANAGER AT THE TIME OF CONSTRUCTION. THE LARGER SIGN SHALL BE PLACED IN PLAIN SIGHT AT ALL ROOF ACCESS LOCATIONS AND ON ALL BARRICADES. THE SMALLER SIGN SHALL BE PLACED ON THE ANTENNA ENCLOSURES IN A MANNER THAT IS EASILY SEEN BY ANY PERSON ON THE ROOF. WARNING SIGNS SHALL COMPLY w/ ANSI C95.2 COLOR, SYMBOL, AND CONTENT CONVENTIONS. ALL SIGNS SHALL HAVE AT&T'S NAME AND THE COMPANY CONTACT INFORMATION (e.g. TELEPHONE NUMBER) TO ARRANGE FOR ACCESS TO THE RESTRICTED AREAS. THIS TELEPHONE NUMBER SHALL BE PROVIDED TO THE CONTRACTOR BY THE AT&T CONSTRUCTION PROJECT MANAGER AT THE TIME OF CONSTRUCTION.
- PHOTOS OF ALL STRIPING, BARRICADES & SIGNAGE SHALL BE PART OF THE CONTRACTORS CLOSE OUT PACKAGE & SHALL BE TURNED INTO THE AT&T CONSTRUCTION PACKAGE & SHALL BE TURNED INTO THE AT&T CONSTRUCTION PROJECT MANAGER AT THE END OF CONSTRUCTION. STRIPING SHALL BE DONE w/ FADE RESISTANT YELLOW SAFETY PAINT IN A CROSS-HATCH PATTERN AS DETAILED BY THE CONSTRUCTION DRAWINGS. ALL BARRICADES SHALL BE MADE OF AN RF FRIENDLY MATERIAL SO AS NOT TO BLOCK OR INTERFERE w/ THE OPERATION OF THE ANTENNAS. BARRICADES SHALL BE PAINTED w/ FADE RESTRAINT YELLOW SAFETY PAINT. THE CONTRACTOR SHALL PROVIDE ALL RF FRIENDLY BARRICADES NEEDED, & SHALL PROVIDE THE AT&T CONSTRUCTION PROJECT MANAGER w/ A DETAILED SHOP DRAWING OF EACH BARRICADE. UPON CONSTRUCTION COMPLETION.

1 GENERAL NOTES
N.T.S.

PREPARED FOR



NEW CINGULAR WIRELESS PCS,
 LLC ("AT&T")
 19801 SW 72ND AVE., STE. 200
 TUALATIN, OR 97062

Vendor:



23 MAUCHLY #110
 IRVINE, CA 92618
 JS PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
 928 STURM AVE
 WALLA WALLA, WA 99362
 PARCEL ID:
 47662 & 47722

DRAWN BY: RC

CHECKED BY: EVR

REV	DATE	DESCRIPTION
0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV DATE DESCRIPTION

Licenser:

Sheet Title:

SITE SIGNAGE

Sheet Number:

GN-3

EnerSys SAFETY DATA SHEET **HAWKER** Form #: SDS 853026
 Revised: AB
 Supersedes: AA (06-16-16)
 ECO #: 1001828

II. PRODUCT IDENTIFICATION
Chemical Name (as used on label): Sealed Lead Battery
Chemical Family/Classification: Sealed Lead Battery
 Aerosols and defense batteries manufactured using factory modified versions of Cyclon®, Genes®, SBS, XE®, Ammass® Phas®, or Large TPPL.
Synonyms: Sealed Lead Acid Battery, VRLA Battery
Manufacturer's Name/Address: EnerSys Energy Products Inc. (Formerly Hawker Energy Products Inc.)
 617 N. Ridgeway Drive
 Farmingdale, MD 20640-0101
ChemTREC/DOMESTIC: 809-424-0300 **ChemTREC INTL:** 703-527-3877

HEALTH	ENVIRONMENTAL	PHYSICAL
Acute Toxicity (Oral/Dermal/Inhalation) Category 4 Skin Corrosion/Irritation Category 1A Eye Damage Category 1 Reproductive Category 1A Carcinogenicity (lead compounds) Category 1B Carcinogenicity (acid mist) Category 1A Specific Target Organ Toxicity (repeated exposure) Category 2	Aquatic Chronic 1 Aquatic Acute 1	Explosive Chemical, Division 1.3

GHS LABEL:

HEALTH	ENVIRONMENTAL	PHYSICAL

Hazard Statements: DANGER! Causes severe skin burns and serious eye damage. May damage fertility or the unborn child if ingested or inhaled. May cause cancer if ingested or inhaled. Causes damage to central nervous system, blood and kidneys through prolonged or repeated exposure. May form explosive air/gas mixture during charging. Extremely flammable gas (hydrogen). Explosive, fire, blast, or projection hazard. May cause harm to breast-fed children. Harmful if swallowed, inhaled, or contact with skin. Causes skin irritation, serious eye damage.

Precautionary Statements: Wash thoroughly after handling. Do not eat, drink or smoke when using this product. Wear protective gloves/protective clothing, eye protection/face protection. Avoid breathing dust/fume/gas/mist/vapors/spray. Use only outdoors or in a well-ventilated area. Contact with internal components may cause irritation or severe burns. Avoid contact with internal acid. Irritating to eyes, respiratory system, and skin. Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Avoid contact during pregnancy/while nursing. Keep away from heat, sparks/open flames/hot surfaces. No smoking.

III. COMPOSITION/INFORMATION ON INGREDIENTS

Components	CAS Number	Approximate % by Weight
Inorganic Lead Compound:		
Lead	7439-92-1	45 - 60
Lead Dioxide	1399-60-0	15 - 25
Tin	7440-31-5	0.1 - 0.2
Sulfuric Acid Electrolyte (Sulfuric Acid/Water)	7664-93-9	15 - 20
Case Material:		5 - 10
Polypropylene	9003-07-0	
Polystyrene	9003-53-6	
Styrene Acrylonitrile	9003-54-7	
Acrylonitrile Butadiene Styrene	9003-56-9	
Styrene Butadiene	9003-54-8	
Polyvinylchloride	9002-86-2	
Polycarbonate, Hard Rubber, Polyethylene	9002-88-4	
Polypylene Oxide	25134-01-4	
Polycarbonate/Polyester Alloy	--	
Other:		1 - 2
Absorbent Glass Mat	--	

Page 1

EnerSys SAFETY DATA SHEET **HAWKER** Form #: SDS 853026
 Revised: AB
 Supersedes: AA (06-16-16)
 ECO #: 1001828

IV. FIRST AID MEASURES
Inhalation: Sulfuric Acid: Remove to fresh air immediately. If breathing is difficult, give oxygen. Consult a physician.
 Lead and Lead Compounds (inorganic): For information and emergencies, contact EnerSys Energy Products Environmental, Health & Safety Dept. at 660-429-2165.
Ingestion: Sulfuric Acid: Give large quantities of water; do not induce vomiting or aspiration into the lungs may occur and can cause permanent injury or death; consult a physician.
 Lead: Consult physician immediately.
Skin: Sulfuric Acid: Flush with large amounts of water for at least 15 minutes; remove contaminated clothing completely, including shoes. If symptoms persist, seek medical attention. Wash contaminated clothing before reuse. Discard contaminated shoes.
 Lead: Wash immediately with soap and water.
Eyes: Sulfuric Acid and Lead: Flush immediately with large amounts of water for at least 15 minutes while holding lids. Seek immediate medical attention if eyes have been exposed directly to acid.

V. FIRE FIGHTING MEASURES
Flash Point: N/A **Flammable Limits:** LEL = 4.1% (Hydrogen Gas) UEL = 74.2% (Hydrogen Gas)
Extinguishing Media: Carbon dioxide, foam, dry chemical. Avoid breathing vapors. Use appropriate media for surrounding fire.
Special Fire Fighting Procedures: If batteries are on charge, shut off power. Use positive pressure, self-contained breathing apparatus. Water applied to electrolyte generates heat and causes it to splatter. Wear acid-resistant clothing, gloves, face and eye protection. Note that strings of series connected batteries may still pose risk of electric shock even when charging equipment is shut down.
Unusual Fire and Explosion Hazards: Highly flammable hydrogen gas is generated during charging and operation of batteries. To avoid risk of fire or explosion, keep sparks or other sources of ignition away from batteries. Do not allow metallic materials to simultaneously contact negative and positive terminals of cells and batteries. Follow manufacturer's instructions for installation and service.

VI. ACCIDENTAL RELEASE MEASURES
Spill or Leak Procedures: Stop flow of material, contain/absorb small spills with dry sand, earth, and vermiculite. Do not use combustible materials. If possible, carefully neutralize spilled electrolyte with soda ash, sodium bicarbonate, lime, etc. Wear acid-resistant clothing, boots, gloves, and face shield. Do not allow discharge of unneutralized acid to sewer. Acid must be managed in accordance with local, state, and federal requirements. Consult state environmental agency and/or federal EPA.

VII. HANDLING AND STORAGE
Handling: Unless involved in recycling operations, do not brush the casing or empty the contents of the battery. There may be increasing risk of electric shock from strings of connected batteries. Keep containers tightly closed when not in use. If battery case is broken, avoid contact with internal components. Keep vent caps on and cover terminals to prevent short circuits. Place cardboard between layers of stacked automotive batteries to avoid damage and short circuits. Keep away from combustible materials, organic chemicals, reducing substances, metals, strong oxidizers and water. Use banding or stretch wrap to secure items for shipping.
Storage: Store batteries in cool, dry, well-ventilated areas with impervious surfaces and adequate containment in the event of spills. Batteries should also be stored under roof for protection against adverse weather conditions. Separate from incompatible materials. Store and handle only in areas with adequate water supply and spill control. Avoid damage to containers. Keep away from fire, sparks and heat. Keep away from metallic objects which could bridge the terminals on a battery and create a dangerous short-circuit.
Charging: There is a possible risk of electric shock from charging equipment and from strings of series connected batteries, whether or not being charged. Shut-off power to chargers whenever not in use and before detachment of any circuit connections. Batteries being charged will generate and release flammable hydrogen gas. Charging area should be ventilated. Keep battery vent caps in position. Prohibit smoking and avoid creation of flames and sparks nearby. Wear face and eye protection when near batteries being charged.

Page 2

EnerSys SAFETY DATA SHEET **HAWKER** Form #: SDS 853026
 Revised: AB
 Supersedes: AA (06-16-16)
 ECO #: 1001828

VIII. EXPOSURE CONTROLS/PERSONAL PROTECTION
Exposure Limits (mg/m3): Note: N.E. = Not Established

INGREDIENTS (Chemical/Common Names)	OSHA PEL	ACGIH	US NIOSH	Quebec PELV	Ontario OEL	EU OEL
Lead and Lead Compounds (inorganic)	0.05	0.05	0.05	0.05	0.05	0.15 (d)
Tin	2	2	2	2	2	N.E.
Sulfuric Acid Electrolyte	1	0.2	1	1	0.2	0.05 (a)
Polypropylene	N.E.	N.E.	N.E.	N.E.	N.E.	N.E.
Polystyrene	N.E.	N.E.	N.E.	N.E.	N.E.	N.E.
Styrene Acrylonitrile	N.E.	N.E.	N.E.	N.E.	N.E.	N.E.
Acrylonitrile Butadiene Styrene	N.E.	N.E.	N.E.	N.E.	N.E.	N.E.
Styrene Butadiene	N.E.	N.E.	N.E.	N.E.	N.E.	N.E.
Polyvinylchloride	N.E.	N.E.	N.E.	N.E.	1	N.E.
Polycarbonate, Hard Rubber, Polyethylene	N.E.	N.E.	N.E.	N.E.	N.E.	N.E.
Polyphenylene Oxide	N.E.	N.E.	N.E.	N.E.	N.E.	N.E.
Polycarbonate/Polyester Alloy	N.E.	N.E.	N.E.	N.E.	N.E.	N.E.
Rubber, Polyethylene	N.E.	N.E.	N.E.	N.E.	N.E.	N.E.
Absorbent Glass Mat	N.E.	N.E.	N.E.	N.E.	N.E.	N.E.

NOTES:
 (a) As inhalable aerosol
 (c) Thoracic fraction

Engineering Controls (Ventilation): Store and handle in well-ventilated area. If mechanical ventilation is used, components must be acid-resistant. Handle batteries cautiously to avoid spills. Make certain vent caps are on securely. Avoid contact with internal components. Wear protective clothing, eye and face protection when filling, charging or handling batteries. Do not allow metallic materials to simultaneously contact both the positive and negative terminals of the batteries. Charge the batteries in areas with adequate ventilation. General dilution ventilation is acceptable.

Respiratory Protection (NIOSH/MSHA approved): None required under normal conditions. When concentrations of sulfuric acid mist are known to exceed the PEL, use NIOSH or MSHA-approved respiratory protection.

Skin Protection: If battery case is damaged, use rubber or plastic acid-resistant gloves with elbow-length gauntlet, acid-resistant apron, clothing and boots.

Eye Protection: If battery case is damaged, use chemical goggles or face shield.

Other Protection: Under severe exposure emergency conditions, wear acid-resistant clothing and boots.

IX. PHYSICAL AND CHEMICAL PROPERTIES

Properties Listed Below are for Electrolytes	Boiling Point:	203 - 240° F	Specific Gravity (H2O = 1):	1.215 to 1.350
Melting Point:	N/A	Vapor Pressure (mm Hg):	10	
Solubility in Water:	100%	Vapor Density (AIR = 1):	Greater than 1	
Evaporation Rate: (Butyl Acetate = 1)	Less than 1	% Volatile by Weight:	N/A	
LEL (Lower Explosive Limit)	4.1% (Hydrogen)	Flash Point:	Below room temperature (as hydrogen gas)	
UEL (Upper Explosive Limit)	74.2% (Hydrogen)	UFL (Upper Explosive Limit)	74.2% (Hydrogen)	

Appearance and Odor: Manufactured article; no apparent odor. Electrolyte is a clear liquid with a sharp, penetrating, pungent odor.

Page 3

NOTE:
 1. FOR INFORMATION PURPOSES ONLY.

PREPARED FOR

AT&T
 NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
 19801 SW 72ND AVE., STE. 200
 TUALATIN, OR 97062

Vendor:

J5 INFRASTRUCTURE PARTNERS

23 MAUCHLY #110
 IRVINE, CA 92618
 J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
 928 STURM AVE
 WALLA WALLA, WA 99362
 PARCEL ID:
 47662 & 47722

DRAWN BY: RC
 CHECKED BY: EVR

REV	DATE	DESCRIPTION
0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

Licensors:

Sheet Title:
MATERIAL SAFETY DATA SHEET & LEAD ACID BATTERY -1

Sheet Number:
GN-4

EnerSys SAFETY DATA SHEET **HAWKER** Form #: SDS 853026
 Revised: AB
 Supersedes: AA (06-16-16)
 ECO #: 1001828

X. STABILITY AND REACTIVITY
Stability: Stable 2, Unstable
This product is stable under normal conditions at ambient temperature.
Conditions to Avoid: Prolonged overcharge; sources of ignition
Incompatibility: Materials to avoid: Sulfuric Acid: Contact with combustibles and organic materials may cause fire and explosion. Also reacts violently with strong reducing agents, metals, sulfur trioxide gas, strong oxidizers and water. Contact with metals may produce toxic sulfur dioxide fumes and may release flammable hydrogen gas.
 Lead Compounds: Avoid contact with strong acids, bases, halides, halogenates, potassium nitrate, permanganate, peroxides, nascent hydrogen and reducing agents.
Hazardous Decomposition Products: Sulfuric Acid: Sulfur trioxide, carbon monoxide, sulfuric acid mist, sulfur dioxide, and hydrogen sulfide.
 Lead Compounds: High temperatures likely to produce toxic metal fume, vapor, or dust; contact with strong acid or base or presence of nascent hydrogen may generate highly toxic arsine gas.
Hazardous Polymerization: Will not occur

XI. TOXICOLOGICAL INFORMATION
Routes of Entry: Sulfuric Acid: Harmful by all routes of entry.
 Lead Compounds: Hazardous exposure can occur only when product is heated, oxidized or otherwise processed or damaged to create dust, vapor or fume. The presence of nascent hydrogen may generate highly toxic arsine gas.
Inhalation: Sulfuric Acid: Breathing of sulfuric acid vapors or mists may cause severe respiratory irritation.
 Lead Compounds: Inhalation of lead dust or fumes may cause irritation of upper respiratory tract and lungs.
Ingestion: Sulfuric Acid: May cause severe irritation of mouth, throat, esophagus and stomach.
 Lead Compounds: Acute ingestion may cause abdominal pain, nausea, vomiting, diarrhea and severe cramping. This may lead rapidly to systemic toxicity and must be treated by a physician.
Skin Contact: Sulfuric Acid: Severe irritation, burns and ulceration.
 Lead Compounds: Not absorbed through the skin.
Eye Contact: Sulfuric Acid: Severe irritation, burns, cornea damage, and blindness.
 Lead Compounds: May cause eye irritation.

Effects of Overexposure - Acute: Sulfuric Acid: Severe skin irritation, damage to cornea, upper respiratory irritation.
 Lead Compounds: Symptoms of toxicity include headache, fatigue, abdominal pain, loss of appetite, muscle aches and weakness, sleep disturbance and irritability.
Effects of Overexposure - Chronic: Sulfuric Acid: Possible erosion of tooth enamel, inflammation of nose, throat and bronchial tubes.
 Lead Compounds: Anemic neuropathy, particularly of the motor nerves, with wrist drop; kidney damage; reproductive changes in males and females. Repeated exposure to lead and lead compounds in the workplace may result in nervous system toxicity. Some toxicologists report abnormal conduction velocities in persons with blood lead levels of 50mg/100 ml or higher. Heavy lead exposure may result in central nervous system damage, encephalopathy and damage to the blood-forming (hematopoietic) tissues.

Carcinogenicity: Sulfuric Acid: The International Agency for Research on Cancer (IARC) has classified "strong inorganic acid mist containing sulfuric acid" as a Group 1 carcinogen, a substance that is carcinogenic to humans. This classification does not apply to liquid forms of sulfuric acid or sulfuric acid solutions contained within a battery. Inorganic acid mist (sulfuric acid mist) is not generated under normal use of this product. Misuse of the product, such as overcharging, may result in the generation of sulfuric acid mist.
 Lead Compounds: Lead is listed as a Group 1A carcinogen, likely to initiate at extreme doses. Per the guidance found in OSHA 29 CFR 1910.1200 Appendix E, this is approximately equivalent to GHS Category 1B. Proof of carcinogenicity in humans is lacking at present.

Medical Conditions Generally Aggravated by Exposure: Overexposure to sulfuric acid mist may cause lung damage and aggravate pulmonary conditions. Contact of sulfuric acid with skin may aggravate diseases such as eczema and contact dermatitis. Lead and its compounds can aggravate some forms of kidney, liver and neurological diseases.

Page 4

EnerSys SAFETY DATA SHEET **HAWKER** Form #: SDS 853026
 Revised: AB
 Supersedes: AA (06-16-16)
 ECO #: 1001828

Acute Toxicity: Inhalation LD50: Electrolyte, LC50 rat: 375 mg/m3; LC50: guinea pig: 510 mg/m3
 Elemental Lead: Acute Toxicity Point Estimate = 4500 ppmv (based on lead bullion)
Oral LD50: Electrolyte, rat: 2140 mg/kg
 Elemental Lead: Acute Toxicity Estimate (ATE) = 500 mg/kg body weight (based on lead bullion)

Additional Health Data: All heavy metals, including the hazardous ingredients in this product, are taken into the body primarily by inhalation and ingestion. Most inhalation problems can be avoided by adequate precautions such as ventilation and respiratory protection covered in Section 8. Follow good personal hygiene to avoid inhalation and ingestion: wash hands, face, neck and arm thoroughly before eating, smoking or leaving the workplace. Keep contaminated clothing out of non-contaminated areas, or wear cover clothing when in such areas. Restrict the use and presence of food, tobacco and cosmetics to non-contaminated areas. Work clothes and work equipment used in contaminated areas must remain in designated areas and never taken home or laundered with personal non-contaminated clothing. This product is intended for industrial use only and should be isolated from children and their environment.
 The 19th Amendment to EC Directive 67/548/EEC classified lead compounds, but not lead in metal form, as possibly toxic to reproduction. Risk phrase 61: May cause harm to the unborn child, applies to lead compounds, especially soluble forms.

XII. ECOLOGICAL INFORMATION
Environmental Fate: Lead is very persistent in soil and sediments. No data on environmental degradation. Mobility of metallic lead between ecological compartments is slow. Bioaccumulation of lead occurs in aquatic and terrestrial animals and plants but little bioaccumulation occurs through the food chain. Most studies include lead compounds and not elemental lead.
Environmental Toxicity-Aquatic Toxicity: Sulfuric acid: 24-hr LC50, freshwater fish (Brachydanio rerio): 82 mg/L
 96-hr LOEC, freshwater fish (Cyprinus carpio): 22 mg/L
 Lead: 48-hr LC50 (modeled for aquatic invertebrates): <1 mg/L, based on lead bullion

Additional Information: No known effects on stratospheric ozone depletion.
 - Volatile organic compounds: 0% (by volume)
 - Water Endangering Class (WGC): NA

XIII. DISPOSAL CONSIDERATIONS (UNITED STATES)
Spent batteries: Send to secondary lead smelter for recycling. Spent lead-acid batteries are not regulated as hazardous waste when the requirements of 40 CFR Section 266.80 are met. This should be managed in accordance with approved local, state and federal requirements. Consult state environmental agency and/or federal EPA.
Electrolyte: Place neutralized slurry into sealed containers and handle as applicable with state and federal regulations. Large waste-related spills, after neutralization and testing, should be managed in accordance with approved local, state and federal regulations. Consult state environmental agency and/or federal EPA.
 Following local, State/Provincial, and Federal/National regulations applicable to end-of-life characteristics will be the responsibility of the end-user.

Page 5

EnerSys SAFETY DATA SHEET **HAWKER** Form #: SDS 853026
 Revised: AB
 Supersedes: AA (06-16-16)
 ECO #: 1001828

XIV. TRANSPORT INFORMATION
U.S. DOT: Exempted from the hazardous materials regulations (HMR) because the batteries meet the requirements of 49 CFR 173.159(f) and 49 CFR 173.159a of the U.S. Department of Transportation's HMR. Battery and outer package must be marked "NONSPILLABLE" or "NONSPILLABLE BATTERY". Battery terminals must be protected against short circuits.
IATA Dangerous Goods Regulations DGR: Exempted from the dangerous goods regulations because the batteries meet the requirements of Packing Instruction 872 and Special Provision A67 of the International Air Transportation Association (IATA) Dangerous Goods Regulations and International Civil Aviation Organization (ICAO) Technical Instructions. Battery Terminals must be protected against short circuits.
 The words "NOT RESTRICTED", SPECIAL PROVISION A67 must be provided when the air waybill is issued.
IMDG: Exempted from the dangerous goods regulations for transport by sea because the batteries meet the requirements of Special Provision 258 of the International Maritime Dangerous Goods (IMDG) CODEX. Battery terminals must be protected against short circuits.
Requirements for Safe Shipping and Handling of Cyclon Cells: Warning - Electrical Fire Hazard - Protect against shorting. Terminals can short and cause a fire if not insulated during shipping. Cyclon product must be labeled "NONSPILLABLE" during shipping. Follow all federal shipping regulations. See section IX of this sheet and CFR 49 Parts 171 through 180, available online at www.govaccess.gov.
Requirements for Shipping Cyclon Product as Single Cells: Protective caps or other durable inert material must be used to insulate each terminal of each cell unless cells are shipping in the original packaging from EnerSys. In full box quantities, protective caps are available for all cell sizes by contacting EnerSys Customer Service at 1-800-964-2837.
Requirements for Shipping Cyclon Product Assembled Into Multicell Batteries: Assembled batteries must have short circuit protection during shipping. Exposed terminals, connectors, or lead wires must be insulated with a durable inert material to prevent exposure during shipping.

XV. REGULATORY INFORMATION
EPA SARA Title III: Section 302 (PCRA) Extremely Hazardous Substances (EHS): Sulfuric acid is a listed "Extremely Hazardous Substance" under EPCRA, with a Threshold Planning Quantity (TPQ) of 1,000 lbs. EPCRA Section 302 notification is required if 1,000 lbs or more of sulfuric acid is present at one site (40 CFR 370.10). For more information consult 40 CFR Part 355. The quantity of sulfuric acid will vary by battery type. Contact your EnerSys representative for additional information.
 Section 304 (CERCLA) Hazardous Substances: Reportable Quantity (RQ) for spilled 100% sulfuric acid under CERCLA (Superfund) and EPCRA (Emergency Planning and Community Right to Know Act) is 1,000 lbs. State and local reportable quantities for spilled sulfuric acid may vary.
 Section 311.312 Hazard Categories: EPCRA Section 312 Tier Two reporting is required for non-automotive batteries if sulfuric acid is present in quantities of 500 lbs or more and/or if lead is present in quantities of 10,000 lbs or more. For more information consult 40 CFR 370.10 and 40 CFR 370.40.
 Section 313 (EPCRA) Toxic Substances: 40 CFR section 372.38 (b) states: "If a toxic chemical is present in an article at a covered facility, a person is not required to consider the quantity of the toxic chemical present in such article when determining whether an applicable threshold has been met under § 372.25, § 372.27, or § 372.28 or determining the amount of release to be reported under § 372.30. This exemption applies whether the person received the article from another person or the person produced the article. However, this exemption applies only to the quantity of the toxic chemical present in the article."
Supplier Notification: This product contains toxic chemicals, which may be reportable under EPCRA Section 313 Toxic Chemical Release Inventory (Form R) requirements. If you are a manufacturing facility under SIC codes 20 through 39, the following information is provided to enable you to complete the required reports.

Toxic Chemical	CAS Number	Approximate % by Wt.
Lead	7439-92-1	45 - 60
Sulfuric Acid Electrolyte (Sulfuric Acid/Water)	7664-93-9	15 - 20
Tin	7440-31-5	0.1 - 0.2

See 40 CFR Part 370 for more details.
 If you distribute this product to other manufacturers in SIC Codes 20 through 39, this information must be provided with the first shipment of each calendar year.
 The Section 313 supplier notification requirement does not apply to batteries, which are "consumer products".

Page 6

SAFETY DATA SHEET Form #: SDS 853026 Revised: AB Supersedes: AA (06/16/16) ECO #: 1901828	
TSCA: TSCA Section 8b - Inventory Status: All chemicals comprising this product are either exempt or listed on the TSCA Inventory. TSCA Section 12b (40 CFR Part 707.600b): No notice of export will be required for articles, except PCB articles, unless the Agency so requires in the context of individual section 5, 6, or 7 actions. TSCA Section 13 (40 CFR Part 707.20): No import certification required (EPA 305-B-99-001, June 1999, Introduction to the Chemical Import Requirements of the Toxic Substances Control Act, Section IV.A).	
RCRA: Spent Lead Acid Batteries are subject to streamlined handling requirements when managed in compliance with 40 CFR section 266.80 or 40 CFR part 273. Waste sulfuric acid is a characteristic hazardous waste, EPA hazardous waste number D002 (corrosivity) and D008 (lead).	
CAA: EnerSys supports preventative actions concerning ozone depletion in the atmosphere due to emissions of CFCs and other ozone depleting chemicals (ODCs), defined by the USEPA as Class 1 substances. Pursuant to Section 611 of the Clean Air Act Amendments (CAAA) of 1990, finalized on January 19, 1993, EnerSys established a policy to eliminate the use of Class I ODCs prior to the May 15, 1993 deadline.	
STATE REGULATIONS (US): Provision 65: Warning: Battery posts, terminals and related accessories contain lead and lead compounds, chemicals known to the State of California to cause cancer and reproductive harm. Batteries also contain other chemicals known to the State of California to cause cancer. Wash hands after handling.	
INTERNATIONAL REGULATIONS: Distribution into Quebec to follow Canadian Controlled Product Regulations (CPR) 24(1) and 24(2). Distribution into the EU to follow applicable Directives to the Use, Import/Export of the product as sold.	
ENVIRONMENTAL INFORMATION: Revised: All (06/25/17)	
SDS Hazard Rating for Sulfuric Acid: Flammability (Red) = 0 Health (Blue) = 3 Reactivity (Yellow) = 2 Sulfuric acid is water-reactive if concentrated.	
DISCLAIMER: This Safety Data Sheet is created by the manufacturer to comply with the requirements of 29 CFR 1910.1200. To the extent allowed by law, the manufacturer hereby expressly disclaims any liability to any third party, including users of this product, including, but not limited to, consequential or other damages, arising out of the use of or reliance on, this Safety Data Sheet.	

PowerSafe SBS Front and Top Terminal
 Telecommunications NEBS™ Compliant*

Battery Performance Specifications

Visit us at www.enersys.com RESERVE POWER NEBS™ Compliant (EN60336) Core Industries Following: SBS 80, SBS 800, SBS 804, SBS C11, SBS 145, SBS 190, SBS 190, SBS 190, SBS 190, SBS 190F and SBS 112

Publication No: US-SBS-P8-AD January 2017

SBS 170F BATTERY SPECS (1 UNIT)			
LENGTH =	22.1"		
WIDTH =	4.92"		
HEIGHT =	11.1"		
WEIGHT =	116 LBS		
SBS 190F BATTERY SPECS (1 UNIT)			
LENGTH =	22.1"		
WIDTH =	4.92"		
HEIGHT =	12.4"		
WEIGHT =	132 LBS		

Features and Benefits

- Capacity range 7-361Ah
- 6V and 12V monobloc configurations
- Multiple string configurations available
- Two year shelf life
- SR-4228 compliant
- Proven long service life
- High energy density and cycling capability

Construction

- Utilizes Thin Plate Pure Lead (TPPL) technology. Thin positive grids are produced from high purity lead from a unique manufacturing process to maximize corrosion resistance and service life while increasing energy density
- Separators are Absorbent Glass Mat (AGM) made from high purity, superior quality fibers. The electrolyte is absorbed within the AGM, preventing acid spills in case of accidental damage
- Electrolyte is produced from extremely high purity acid to reduce self discharge rates and float currents
- Container and cover in flame retardant UL94V0 material, highly resistant to shock and vibration
- Front terminal batteries use tin-plated copper terminals. Top terminal batteries use a copper alloy insert
- Self-regulating one way pressure relief valves prevent ingress of atmospheric oxygen

Installation and Operation

- Space efficient footprint
- Valve Regulated Lead Acid (VRLA) design reduces maintenance requirements
- Lifting handles for easy handling
- Greater than 10 year life expectancy in float service at 77°F (25°C)
- TPPL technology provides increased active material surface area which yields increased energy density
- Operating temperature: -40°F (-40°C) to 122°F (50°C) Recommended temperature: 68°F (20°C) to 86°F (30°C)

Standards

- Approved as non-hazardous cargo for ground, sea and air transportation in accordance with US DOT Regulation 49 and ICAO & IATA Packing Instruction 806. Please see our SDS for complete details at www.enersys.com
- Complies with Telcordia® SR-4228, Network Equipment Building System (NEBS™) Criteria Levels
- The management systems governing the manufacture of this product are ISO 9001:2008 and ISO 14001:2004 certified

General Specifications

Battery Type	Number of Cells	Nominal Voltage (V)	Nominal Capacity		Nominal Dimensions			Typical Weight (lbs)	Short Circuit Current (Amps)	Internal Resistance (mΩ)	Terminals	Electrolyte (1.265 SG)		Pure Acid (1.50 SG)		Lead Weight (per lb)									
			1hr Rate @ 25°C	1hr Rate @ 20°C	Length (in)	Width (in)	Height (in)					Volume (per Mic)	Weight (per Mic)	Volume (per Mic)	Weight (per Mic)										
SBS 8*	6	12	7	5.43	138	3.38	86.0	3.90	89.0	5.85	2.70	455	27.1	MMF	0.10	0.38	1.88	0.48	0.03	0.11	0.43	0.18	4.26	1.83	
SBS 15	6	12	14	14	7.87	200	3.03	77.0	5.51	140	11.5	5.20	891	13.5	MMF	0.20	0.75	2.14	0.87	0.06	0.21	0.85	0.38	7.83	3.55
SBS 30	6	12	26	26	9.84	250	3.82	97.0	6.14	156	20.9	9.50	1556	7.90	MM	0.40	1.51	4.33	1.98	0.11	0.43	1.72	0.78	15.5	7.04
SBS HB30	6	12	26	26	9.84	250	3.82	97.0	6.14	156	21.2	9.60	1556	7.90	harness	0.40	1.51	4.33	1.98	0.11	0.43	1.72	0.78	15.5	7.04
SBS 40	6	12	38	38	9.84	250	3.82	97.0	6.14	206	29.1	13.2	2184	5.60	MM	0.59	2.23	6.39	2.90	0.17	0.63	2.53	1.15	21.2	9.61
SBS 60	6	12	51	51	8.66	220	4.76	121	10.3	261	40.8	18.5	2618	4.40	MM	0.85	3.22	9.21	4.17	0.24	0.91	3.65	1.66	28.1	13.2
SBS 110	3	6	116	115	7.87	200	8.19	208	9.41	239	46.7	21.2	3804	1.70	MM	0.85	3.60	10.3	4.67	0.27	1.01	4.08	1.86	31.6	14.3
SBS 130	3	6	133	132	7.87	200	8.19	208	9.41	239	50.0	22.7	4111	1.40	MM	0.88	3.70	10.6	4.80	0.28	1.04	4.20	1.90	34.2	15.5
SBS 300	1	2	307	310	7.87	200	8.19	208	9.41	239	47.8	21.7	8700	0.23	MM	0.85	3.60	10.3	4.67	0.27	1.01	4.08	1.86	31.9	14.5
SBS 380	1	2	361	360	7.87	200	8.19	208	9.41	239	51.1	23.2	11101	0.18	MM	0.80	3.39	9.70	4.40	0.25	0.95	3.85	1.75	34.7	15.7
SBS J13	6	12	12	12	6.89	175	3.27	83.0	5.08	129	11.5	5.20	957	13.0	MMF	0.18	0.68	1.95	0.88	0.05	0.19	0.77	0.35	8.11	3.68
SBS J16	6	12	15	15	7.13	181	2.99	76.0	6.57	167	14.8	6.70	1111	11.0	MMF	0.23	0.87	2.49	1.13	0.06	0.25	0.89	0.45	11.0	5.00
SBS J30	6	12	26	26	6.54	166	6.89	175	4.92	125	26.0	11.8	1766	7.00	MMF	0.39	1.48	4.22	1.92	0.11	0.42	1.68	0.76	18.1	8.19
SBS J40	6	12	39	39	7.76	197	6.50	165	6.69	170	35.1	15.9	2400	5.20	MMF	0.61	2.31	6.61	3.00	0.17	0.65	2.62	1.19	27.6	12.5
SBS J70	6	12	64	64	13.0	329	6.54	166	6.85	174	60.8	27.6	3500	3.50	MMF	0.88	3.71	10.6	4.81	0.28	1.04	4.21	1.91	44.4	20.2
SBS B6*	6	12	31	31	11.0	280	3.82	97.0	6.26	158	22.7	10.3	1270	10.0	MMF	0.37	1.42	4.06	1.84	0.11	0.40	1.61	0.73	15.6	7.08
SBS B10*	6	12	38	38	11.0	280	3.82	97.0	7.24	184	26.0	11.8	1390	9.00	MMF	0.48	1.80	5.15	2.34	0.13	0.51	2.04	0.93	17.7	8.03
SBS B14*	6	12	62	62	11.0	280	3.82	97.0	10.4	264	42.1	19.1	1800	7.00	MMF	0.78	2.95	8.45	3.83	0.22	0.83	3.25	1.52	28.6	13.4
SBS C11*	6	12	91	92	15.6	395	4.13	105	10.4	264	61.7	28.0	2300	5.50	MMF	1.28	4.85	13.9	6.29	0.36	1.38	5.50	2.49	43.3	19.7
SBS 100*	6	12	100	100	15.6	395	4.25	108	11.3	287	71.9	32.6	2210	5.60	MMF	1.34	5.09	14.6	6.60	0.38	1.43	5.77	2.62	48.7	22.6
SBS 145*	6	12	145	145	16.9	429	6.77	172	8.37	238	105	47.6	4100	3.00	MMF	2.21	8.37	23.9	10.9	0.62	2.35	9.48	4.31	78.5	36.1
SBS B61*	6	12	31	31	11.9	303	3.82	97.0	6.26	158	22.7	10.3	1270	10.0	MM	0.37	1.42	4.06	1.84	0.11	0.40	1.61	0.73	15.6	7.08
SBS B10F*	6	12	38	38	11.9	303	3.82	97.0	7.24	184	26.2	12.8	1390	9.00	MMF	0.48	1.80	5.15	2.34	0.13	0.51	2.04	0.93	17.7	8.03
SBS B14F*	6	12	62	62	11.9	303	3.82	97.0	10.4	264	42.1	19.1	1800	7.00	MM	0.78	2.95	8.45	3.83	0.22	0.83	3.25	1.52	28.6	13.4
SBS C11F*	6	12	91	92	16.4	417	4.13	105	10.1	256	61.8	27.9	2300	5.50	MM	1.28	4.85	13.9	6.29	0.36	1.38	5.50	2.49	43.3	19.7
SBS 100F*	6	12	100	100	15.6	395	4.25	108	11.3	287	71.9	32.6	2210	5.60	MM	1.34	5.09	14.6	6.60	0.38	1.43	5.77	2.62	48.7	22.6
SBS 112F*	6	12	112	112	22.1	561	4.92	125	8.98	228	90.4	41.0	2500	5.00	MM	1.71	6.48	18.5	8.41	0.48	1.82	7.25	3.34	58.8	26.8
SBS 145F*	6	12	145	145	17.8	452	6.77	172	10.8	274	116	52.8	3700	2.30	MM	2.25	8.51	24.3	11.8	0.63	2.39	9.66	4.38	72.4	32.8
SBS 165F*	6	12	165	165	17.8	452	6.77	172	10.8	274	116	52.8	3700	2.30	MM	2.45	9.27	26.5	12.8	0.64	2.42	9.72	4.41	82.7	37.5
SBS 170F*	6	12	170	170	22.1	561	4.92	125	11.1	283	116	52.5	3400	4.00	MM	2.66	9.82	27.7	13.3	0.59	2.23	8.89	4.08	82.0	37.2
SBS 190F*	6	12	190	190	22.1	561	4.92	125	12.4	316	132	60.0	3800	3.30	MM	2.34	8.86	25.3	11.5	0.66	2.48	10.1	4.55	95.8	43.4

Dimensions:
 SBS 8 - 60: Top Terminal (Form Factor 1)
 SBS 110-390: Top Terminal (Form Factor 2)
 SBS B6-145: Top Terminal (Form Factor 3)
 SBS B6F-190F: Front Terminal (Form Factor 4)

BATTERY INFORMATION																		
INSTALL STATUS	BATTERY MODEL	TOTAL # OF BATTERY UNITS INSTALLED (EA)	TOTAL ELECTROLYTE VOLUME (GALLONS) PER UNIT	TOTAL ELECTROLYTE WEIGHT (LBS) PER UNIT	TOTAL SULFURIC ACID VOLUME (GALLONS) PER UNIT	TOTAL SULFURIC ACID WEIGHT (LBS) PER UNIT	% SULFURIC ACID BY VOLUME =	TOTAL SULFURIC ACID	TOTAL # OF UNITS x TOTAL SULFURIC ACID VOLUME/UNIT	% SULFURIC ACID BY WEIGHT =	TOTAL SULFURIC ACID	TOTAL # OF UNITS x TOTAL SULFURIC ACID WEIGHT/UNIT	TOTAL SULFURIC ACID BY WEIGHT (LBS) =	TOTAL # OF UNITS x TOTAL SULFURIC ACID WEIGHT/UNIT	TOTAL ELECTROLYTE	TOTAL # OF UNITS x TOTAL ELECTROLYTE VOLUME/UNIT	TOTAL ELECTROLYTE	TOTAL # OF UNITS x TOTAL ELECTROLYTE WEIGHT/UNIT
								VOLUME/UNIT			BY VOLUME (GALLONS) =				WEIGHT/UNIT		BY WEIGHT (LBS) =	
PROPOSED	ENERSYS POWER SAFE - SBS 190F	12	2.34	25.3	0.66	10.1	28.21%	7.92		39.92%	121.20		28.08		28.08		303.60	
TOTAL	N/A	12	2.34	25.3	0.66	10.1	N/A	7.92		N/A	121.20		28.08		28.08		303.60	

NOTE:
1. FOR INFORMATION PURPOSES ONLY.

PREPARED FOR

NEW CINCULAR WIRELESS PCS, LLC ("AT&T")
 19801 SW 72ND AVE., STE. 200
 TUALATIN, OR 97062

Vendor:

23 MAUCHLY #110
 IRVINE, CA 92618

J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
 928 STURM AVE
 WALLA WALLA, WA 99362
 PARCEL ID:
 47662 & 47722

DRAWN BY: RC
 CHECKED BY: EVR

0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD


REV	DATE	DESCRIPTION
-----	------	-------------

Licenser:

Sheet Title:
MATERIAL SAFETY DATA SHEET & LEAD ACID BATTERY -2

Sheet Number:
GN-5

NOTES:
 1. RESIDENCE AND BUILDING LOCATIONS SHOWN BELOW FOR DEPICTION PURPOSES ONLY. ALL DATA GATHERED FROM PUBLIC RECORDS AND GENERATED FROM AERIAL IMAGES.



PREPARED FOR

 NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
 19801 SW 72ND AVE., STE. 200
 TUALATIN, OR 97062

Vendor:

 23 MAUCHLY #110
 IRVINE, CA 92618
 J5 PROJECT ID: P-042954

Issued For:
WL4557
WALLA WALLA
MILL CREEK
 928 STURM AVE
 WALLA WALLA, WA 99362
 PARCEL ID:
 47662 & 47722

DRAWN BY: RC
 CHECKED BY: EVR


REV	DATE	DESCRIPTION
0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV DATE DESCRIPTION

Licensor:

Sheet Title:
AERIAL SITE PLAN


Sheet Number:
A-1.1



EQUIPMENT PLAN (WALK-IN CABINET - WIC)

24"x36" SCALE: 3/4" = 1'-0"


2



DIMENSION PLAN (WALK-IN CABINET - WIC)

24"x36" SCALE: 3/4" = 1'-0"

3




ANTENNA PLAN & SCHEDULE

24"x36" SCALE: 3/8" = 1'-0"

1

RFDS VERSION: FINAL/1.0		(P) ANTENNA SCHEDULE									
DATE UPDATED: 7/30/2020		POS	AZIMUTH	RAD CENTER	MECHANICAL DOWNTILT	ANTENNA MAKE	ANTENNA MODEL	RRH MODEL	SURGE SUPPRESSOR	FEEDER TYPE	FEEDER LENGTH
SECTOR "A"	A1	130	55'-0"	0	CELLMAX	CMA - UBTULBULBHH-6517-17-21-21	(1) B14/12/29 TRIBAND AHLBBA (1) 4T4R B25/66 320W AHFIB				
	A2	130	55'-0"	0	CELLMAX	CMA - UBTULBULBHH-6517-17-21-21	(1) 4T4R B30 100W AHNA				
	A3										
	A4										
SECTOR "B"	B1	250	55'-0"	0	CELLMAX	CMA - UBTULBULBHH-6517-17-21-21	(1) B14/12/29 TRIBAND AHLBBA (1) 4T4R B25/66 320W AHFIB				
	B2	250	55'-0"	0	CELLMAX	CMA - UBTULBULBHH-6517-17-21-21	(1) 4T4R B30 100W AHNA		(1) DC9-48-60-24-8C-EV	(3) DC POWER & (1) 18 PAIR FIBER TRUNK CABLES	±120'
	B3										
	B4										
SECTOR "C"	C1	350	55'-0"	0	CELLMAX	CMA - UBTULBULBHH-6517-17-21-21	(1) B14/12/29 TRIBAND AHLBBA (1) 4T4R B25/66 320W AHFIB				
	C2	350	55'-0"	0	CELLMAX	CMA - UBTULBULBHH-6517-17-21-21	(1) 4T4R B30 100W AHNA				
	C3										
	C4										

PREPARED FOR



Vendor:

J5 INFRASTRUCTURE PARTNERS

23 MAUCHLY #110
IRVINE, CA 92618

J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
928 STURM AVE
WALLA WALLA, WA 99362
PARCEL ID:
47662 & 47722

DRAWN BY: RC
CHECKED BY: EVR

REV	DATE	DESCRIPTION
0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV DATE DESCRIPTION

Licenser:

Sheet Title:
ANTENNA PLAN & SCHEDULE & EQUIPMENT PLAN

Sheet Number:
A-3

NOTE:
1. ALL RELEVANT STRUCTURAL ANALYSIS IS UNDER A SEPARATE PERMIT BY OTHERS.

NOTE:
1. ALL (P) AT&T PANEL ANTENNAS & TOWER MOUNTED EQUIPMENT SHALL BE PAINTED TO MATCH THE PROPOSED MONOPINE
2. ALL (P) AT&T PANEL ANTENNAS SHALL BE COVERED WITH PINE SOCKS
3. AT&T RRU'S, TMA'S, AND SURGE ARRESTORS NOT DEPICTED IN THIS VIEW FOR CLARITY. FOR LOCATIONS OF THESE ITEMS, PLEASE REFER TO PREVIOUS PLANS VIEWS WITHIN THE DRAWING SET

NOTE:
1. ALL RELEVANT STRUCTURAL ANALYSIS IS UNDER A SEPARATE PERMIT BY OTHERS.

NOTE:
1. ALL (P) AT&T PANEL ANTENNAS & TOWER MOUNTED EQUIPMENT SHALL BE PAINTED TO MATCH THE PROPOSED MONOPINE
2. ALL (P) AT&T PANEL ANTENNAS SHALL BE COVERED WITH PINE SOCKS
3. AT&T RRU'S, TMA'S, AND SURGE ARRESTORS NOT DEPICTED IN THIS VIEW FOR CLARITY. FOR LOCATIONS OF THESE ITEMS, PLEASE REFER TO PREVIOUS PLANS VIEWS WITHIN THE DRAWING SET

PREPARED FOR



NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
19801 SW 72ND AVE., STE. 200
TUALATIN, OR 97062

Vendor:



23 MAUCHLY #110
IRVINE, CA 92618

J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
928 STURM AVE
WALLA WALLA, WA 99362
PARCEL ID:
47662 & 47722

DRAWN BY: RC

CHECKED BY: EVR

0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV DATE DESCRIPTION


Licensor:

Sheet Title:

NORTH ELEVATIONS

Sheet Number:

A-4




NORTH ELEVATION (FROM PROPERTY LINE)

24"x36" SCALE: 1/8" = 1'-0"



2



NORTH ELEVATION (COMPOUND)


24"x36" SCALE: 1/8" = 1'-0"



1

NOTE:
1. ALL RELEVANT STRUCTURAL ANALYSIS IS UNDER A SEPARATE PERMIT BY OTHERS.

NOTE:
1. ALL (P) AT&T PANEL ANTENNAS & TOWER MOUNTED EQUIPMENT SHALL BE PAINTED TO MATCH THE PROPOSED MONOPINE
2. ALL (P) AT&T PANEL ANTENNAS SHALL BE COVERED WITH PINE SOCKS
3. AT&T RRU'S, TMA'S, AND SURGE ARRESTORS NOT DEPICTED IN THIS VIEW FOR CLARITY. FOR LOCATIONS OF THESE ITEMS, PLEASE REFER TO PREVIOUS PLANS VIEWS WITHIN THE DRAWING SET




EAST ELEVATION (FROM PROPERTY LINE)

24"x36" SCALE: 1/8" = 1'-0"

NOTE:
1. ALL RELEVANT STRUCTURAL ANALYSIS IS UNDER A SEPARATE PERMIT BY OTHERS.

NOTE:
1. ALL (P) AT&T PANEL ANTENNAS & TOWER MOUNTED EQUIPMENT SHALL BE PAINTED TO MATCH THE PROPOSED MONOPINE
2. ALL (P) AT&T PANEL ANTENNAS SHALL BE COVERED WITH PINE SOCKS
3. AT&T RRU'S, TMA'S, AND SURGE ARRESTORS NOT DEPICTED IN THIS VIEW FOR CLARITY. FOR LOCATIONS OF THESE ITEMS, PLEASE REFER TO PREVIOUS PLANS VIEWS WITHIN THE DRAWING SET



EAST ELEVATION (COMPOUND)

24"x36" SCALE: 1/8" = 1'-0"

PREPARED FOR



NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
19801 SW 72ND AVE., STE. 200
TUALATIN, OR 97062

Vendor:



23 MAUCHLY #110
IRVINE, CA 92618

J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
928 STURM AVE
WALLA WALLA, WA 99362
PARCEL ID:
47662 & 47722

DRAWN BY: RC

CHECKED BY: EVR

0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV DATE DESCRIPTION

Licensors:

Sheet Title:

EAST ELEVATIONS

Sheet Number:

A-5

WWMC 20.160.060 MAINTENANCE REQUIREMENTS:


1. ALL SHRUBS, TREES AND VEGETATIVE MATERIAL USED IN THE SCREENING OR LANDSCAPING SHALL BE PERPETUALLY MAINTAINED IN A HEALTHY, GROWING CONDITION. IRRIGATION SYSTEMS SHALL BE KEPT OPERATIONAL. DEAD, DISEASED OR DYING PLANT MATERIAL SHALL BE REPLACED IMMEDIATELY, AND PLANTING AREAS SHALL BE MAINTAINED REASONABLY FREE OF TRASH AND WEEDS.
2. FENCES USED IN SCREENING AND LANDSCAPING SHALL BE PERPETUALLY MAINTAINED IN AN ATTRACTIVE AND STRUCTURALLY SOUND CONDITION.
3. A MAINTENANCE SURETY IN THE FORM OF A BOND OR OTHER SECURITY ACCEPTABLE TO THE CITY COVERING TWENTY PERCENT OF THE COST OF THE ORIGINAL PLANT MATERIALS IN PLACE MAY BE REQUIRED FOR ONE YEAR FOLLOWING INSTALLATION TO ENSURE COMPLIANCE WITH THIS CODE.
4. IF A MAINTENANCE SURETY IS REQUIRED UNDER THIS SECTION, THE PROPERTY OWNER SHALL PROVIDE THE CITY WITH A NON REVOCABLE NOTARIZED AGREEMENT GRANTING THE CITY AND ITS AGENTS THE RIGHT TO ENTER THE PROPERTY AND PERFORM ANY NECESSARY WORK.
5. THE MAINTENANCE SURETY MAY BE USED BY THE CITY TO PERFORM ANY MAINTENANCE, AND TO REIMBURSE THE CITY FOR DOCUMENTED ADMINISTRATIVE COSTS ASSOCIATED WITH THE MAINTENANCE ACTIVITY.
6. UPON COMPLETION OF THE ONE-YEAR MAINTENANCE PERIOD, THE CITY SHALL PROMPTLY RELEASE THE MAINTENANCE SURETY OR ANY REMAINING PORTION THEREOF.

A BOUNDARY LINE ADJUSTMENT OR LOT COMBINATION WILL BE FILED BETWEEN TRACTS 2-4 TO PROVIDE A TOWER-HEIGHT SETBACK FROM THE NEW NORTH PROPERTY LINE (CONFIGURATION TO BE DETERMINED AND WILL BE AT LEAST 65'-0" AWAY)

(P) AT&T EVERGREEN SHRUB, TYP. (TOTAL-21) WITH A 10'-0" TO 12'-0" MAXIMUM MATURE HEIGHT. (ACTUAL PLANT MATERIAL SELECTED WILL BE SPECIES LISTED IN THE MID-COLUMBIA FORESTRY COUNCIL. AT FINAL APPROVAL, PLANT SPECIES LISTED WILL BE SECURED AT A LOCAL NURSERY(S) FOR CONSTRUCTION. IF LISTED PLANT MATERIAL IS NOT AVAILABLE AT CONSTRUCTION, APPLICANT WILL CONTACT CITY FOR SPECIFIC DIRECTION FOR NEW APPROVED SPECIES IN-KIND.)

(P) AT&T 6'-0" HIGH 28'-0" X 48'-0" CHAIN LINK FENCE W/ PRIVACY SLATS

(P) AT&T EVERGREEN TREE, TYP. (TOTAL-12) WITH A 30' TO 40' MAXIMUM MATURE HEIGHT (ACTUAL PLANT MATERIAL SELECTED WILL BE SPECIES LISTED IN THE MID-COLUMBIA FORESTRY COUNCIL. AT FINAL APPROVAL, PLANT SPECIES LISTED WILL BE SECURED AT A LOCAL NURSERY(S) FOR CONSTRUCTION. IF LISTED PLANT MATERIAL IS NOT AVAILABLE AT CONSTRUCTION, APPLICANT WILL CONTACT CITY FOR SPECIFIC DIRECTION FOR NEW APPROVED SPECIES IN-KIND.)



PREPARED FOR



NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
19801 SW 72ND AVE., STE. 200
TUALATIN, OR 97062

Vendor:



23 MAUCHLY #110
IRVINE, CA 92618

J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
928 STURM AVE
WALLA WALLA, WA 99362
PARCEL ID:
47662 & 47722

DRAWN BY: RC

CHECKED BY: EVR

0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV	DATE	DESCRIPTION
-----	------	-------------












Licenser:

Sheet Title:
CONCEPTUAL
LANDSCAPE PLAN

Sheet Number:

L-1

STURM AVE.



PREPARED FOR

NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
19801 SW 72ND AVE., STE. 200
TUALATIN, OR 97062

Vendor:

23 MAUCHLY #110
IRVINE, CA 92618
J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
928 STURM AVE
WALLA WALLA, WA 99362
PARCEL ID:
47662 & 47722

DRAWN BY: RC
CHECKED BY: EVR


REV	DATE	DESCRIPTION
0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

Licensors:


Sheet Title:
DETAILS

Sheet Number:
D-1


NOTES:
 1. INSTALL FENCING PER ASTM F-567.
 2. INSTALL SWING GATES PER ASTM F-900.
 3. POST & GATE PIPE SIZES ARE INDUSTRY STANDARDS. ALL PIPE TO BE GALV. (HOT DIP, ASTM A120 GRADE "A" STEEL) ALL GATE FRAMES SHALL BE WELDED, ALL WELDING SHALL BE COATED WITH (3) COATS OF COLD GALV. (OR EQUAL)
 4. ALL OPEN POSTS SHALL HAVE END CAPS.




TYPICAL ELEVATION




CORNER ELEVATION




11 CHAIN-LINK FENCE & GATE
 N.T.S.



4 WIC HELICAL WELDMENT ANCHORAGE DETAIL
 N.T.S.




1 CONCRETE FOUNDATION SECTION
 N.T.S.




5 GENERATOR ANCHORAGE DETAIL
 N.T.S.

SHELTER FOUNDATION NOTES:
 1. CONTRACTOR SHALL VERIFY EXTENTS OF FOUNDATIONS AND COORDINATE WITH EQUIPMENT WIC & GENERATOR DRAWINGS. (BY OTHERS)
 2. FASTEN EQUIPMENT WIC & GENERATOR TO FOUNDATION ACCORDING TO EQUIPMENT WIC & GENERATOR DRAWINGS (BY OTHERS)
 3. COORDINATE CONSTRUCTION OF WIC & GENERATOR FOOTING WITH FOOTING OF ADJACENT STRUCTURES. (IF APPLICABLE)




3 CONCRETE FOUNDATION PLAN
 N.T.S.

NOTE:
 1. VERIFY (E) CONDUIT LOCATION AND CONDITION. DO NOT DAMAGE (E) CONDUIT




9 TELCO TRENCH DETAIL
 N.T.S.

NOTE:
 1. VERIFY (E) CONDUIT LOCATION AND CONDITION. DO NOT DAMAGE (E) CONDUIT. (E) CONDUIT TO BE ENCASED IN CONCRETE IF UNDER (N) CONCRETE PAD FOOTING.



6 POWER TRENCH DETAIL
 N.T.S.



12 NOISE BARRIER DETAIL
 N.T.S.

PREPARED FOR

 NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
 19801 SW 72ND AVE., STE. 200
 TUALATIN, OR 97062

Vendor:

 23 MAUCHLY #110
 IRVINE, CA 92618
 J5 PROJECT ID: P-042954

Issued For:
WL4557
WALLA WALLA
MILL CREEK
 928 STURM AVE
 WALLA WALLA, WA 99362
 PARCEL ID:
 47662 & 47722

DRAWN BY: RC
 CHECKED BY: EVR

REV	DATE	DESCRIPTION
0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD


REV DATE DESCRIPTION

Licensors:

Sheet Title:
DETAILS


Sheet Number:
D-3

INTERNAL HEIGHT: 96.5"
 INTERNAL WIDTH: 71.4"
 INTERNAL LENGTH: 71.4"
 EMPTY WEIGHT: 4,500 LBS
 WEIGHT AS INSTALLED: 6,000 LBS



THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF ELECTRO MECHANICAL INDUSTRIES, INC. ANY REPRODUCTION IN PART OR WHOLE WITHOUT THE WRITTEN PERMISSION OF ELECTRO MECHANICAL IND., IS PROHIBITED

REVISIONS				
ZONE	REV	DESCRIPTION	DATE	APPROVED



SURFACE FINISH <input checked="" type="checkbox"/> UNLESS OTHERWISE SPECIFIED		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES		APPROVALS	DATE	ELECTRO MECHANICAL INDUSTRIES, INC. 11230 NEESMAN DRIVE HOUSTON, TEXAS 77065 1-800-451-0050
MATERIAL	TOLERANCES	DRAWN	CHECKED	ENGINEER/DESIGNER	PRODUCTION	
THIRD ANGLE PROJECTION	.01 ± .01 .00 ± .03 .000 ± .005 FRACTIONS ± 1/16 ANGLES ± .25 ALL HOLES: LESS THAN 1.00 ±.012 1.00 AND OVER +.031 -0.12 FRACTIONS ±1/32					
NEXT ASSY	USED ON	SCALE: 1:24	WEIGHT: lbs.	TITLE: WIC LAYOUT WITH 11" EXTENSION SIZE: DRAWING NO. D 1007-0000-0012-Q SHEET 1 OF 1		

PREPARED FOR

 NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
 19801 SW 72ND AVE., STE. 200
 TUALATIN, OR 97062

Vendor:

 23 MAUCHLY #110
 IRVINE, CA 92618
 J5 PROJECT ID: P-042954

Issued For:
WL4557
WALLA WALLA
MILL CREEK
 928 STURM AVE
 WALLA WALLA, WA 99362
 PARCEL ID:
 47662 & 47722

DRAWN BY: RC
 CHECKED BY: EVR

REV	DATE	DESCRIPTION
0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV	DATE	DESCRIPTION

Licensor:

Sheet Title:
WALK-IN CABINET (WIC) DETAILS

Sheet Number:
D-5

NOTE:
1. FOR INFORMATION PURPOSES ONLY.

PREPARED FOR



NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
19801 SW 72ND AVE., STE. 200
TUALATIN, OR 97062

Vendor:



23 MAUCHLY #110
IRVINE, CA 92618
J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
928 STURM AVE
WALLA WALLA, WA 99362
PARCEL ID:
47662 & 47722

DRAWN BY: RC

CHECKED BY: EVR

0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD



REV	DATE	DESCRIPTION
-----	------	-------------

Licensor:

Sheet Title:
ANTENNA MOUNT DETAILS

Sheet Number:
D-6

ITEM	QTY	PART NO.	PART DESCRIPTION	LENGTH	UNIT WT.	NET WT.
1	6	X-LWRM	RING MOUNT WELDMENT		68.81	412.85
2	6	X-RMBP	RING MOUNT BENT PLATE CONNECTION	15 1/2 in	17.02	102.13
3	6	X-VFAPL4	VFA-HD PIVOT PLATE	12 in	15.88	95.30
4	6	X-VFAW	SUPPORT ARM		71.41	428.44
5	30	SCX2	CROSSOVER PLATE	7 in	4.80	143.89
6	6	P284	2-3/8" X 84" SCH 40 GALVANIZED PIPE	84 in	26.91	161.47
7	15	P30120	2-7/8" X 120" (2-1/2" SCH. 40) GALVANIZED PIPE	120 in	58.07	870.99
8	6	P30150	2-7/8" X 150" (2-1/2" SCH. 40) GALVANIZED PIPE	150 in	76.94	461.62
9	12	X-127594	FLAT DISK CLAMP PLATE 4" CENTERS (GALV.)		2.51	30.08
10	24	X-100064	CLAMP (4" V-CLAMP) GALVANIZED		0.92	22.12
11	12	A34212	3/4" X 2-1/2" UNF HEX BOLT (A325)	2 1/2 in	0.48	5.75
12	18	G34FW	3/4" HDG USS FLATWASHER		0.06	1.06
13	12	G34LW	3/4" HDG LOCKWASHER		0.04	0.51
14	12	G34NUT	3/4" HDG HEAVY 2H HEX NUT		0.21	2.55
15	18	G58R-48	5/8" X 48" THREADED ROD (HDG.)		4.18	75.27
16	12	X-UB5300	5/8" X 3" X 5-1/4" X 2-1/2" U-BOLT (HDG.)		1.15	13.79
17	24	A582112	5/8" X 2-1/2" HDG A325 HEX BOLT	2 1/2 in	0.33	8.02
18	24	A582114	5/8" X 2-1/4" HDG A325 HEX BOLT	2 1/4 in	0.31	7.50
19	108	G58LW	5/8" HDG LOCKWASHER		0.03	2.82
20	108	G58NUT	5/8" HDG HEAVY 2H HEX NUT		0.13	14.33
21	120	X-UB1300	1/2" X 3" X 5" X 2" GALV U-BOLT		0.74	88.54
22	24	G12065	1/2" X 6-1/2" HDG HEX BOLT GR5 FULL THREAD	5 1/2 in	0.41	9.83
23	24	G1204	1/2" X 4" HDG HEX BOLT GR5 FULL THREAD	4 in	0.27	6.48
24	288	G12FW	1/2" HDG USS FLATWASHER	3/32 in	0.03	9.82
25	288	G12LW	1/2" HDG LOCKWASHER	1/8 in	0.01	4.00
26	288	G12NUT	1/2" HDG HEAVY 2H HEX NUT		0.07	20.63
TOTAL WT. # 2999.58						



TOLERANCE NOTES
TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE:
SAWED, SHEARED AND GAS CUT EDGES ($\pm 0.030"$)
DRILLED AND GAS CUT HOLES ($\pm 0.030"$) - NO CONING OF HOLES
LASER CUT EDGES AND HOLES ($\pm 0.010"$) - NO CONING OF HOLES
BENDS ARE $\pm 1/2$ DEGREE
ALL OTHER MACHINING ($\pm 0.030"$)
ALL OTHER ASSEMBLY ($\pm 0.060"$)

DESCRIPTION	THREE SECTORS HEAVY WLL FRAME AND MONOPOLE ATTACHMENT HARDWARE WITH FIVE MOUNTING PIPES
CPD NO.	CEK 10/26/2018
DRAWN BY	CUSTOMER
ENG. APPROVAL	BMC 10/29/2018
PART NO.	VFA12-M3-WLL
DWG. NO.	VFA12-M3-WLL




TOLERANCE NOTES
TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE:
SAWED, SHEARED AND GAS CUT EDGES ($\pm 0.030"$)
DRILLED AND GAS CUT HOLES ($\pm 0.030"$) - NO CONING OF HOLES
LASER CUT EDGES AND HOLES ($\pm 0.010"$) - NO CONING OF HOLES
BENDS ARE $\pm 1/2$ DEGREE
ALL OTHER MACHINING ($\pm 0.030"$)
ALL OTHER ASSEMBLY ($\pm 0.060"$)

DESCRIPTION	THREE SECTORS HEAVY WLL FRAME AND MONOPOLE ATTACHMENT HARDWARE WITH FIVE MOUNTING PIPES
CPD NO.	CEK 10/26/2018
DRAWN BY	CUSTOMER
ENG. APPROVAL	BMC 10/29/2018
PART NO.	VFA12-M3-WLL
DWG. NO.	VFA12-M3-WLL



NOTE:
OTHER SECTORS REMOVED FOR CLARITY.




TOLERANCE NOTES
TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE:
SAWED, SHEARED AND GAS CUT EDGES ($\pm 0.030"$)
DRILLED AND GAS CUT HOLES ($\pm 0.030"$) - NO CONING OF HOLES
LASER CUT EDGES AND HOLES ($\pm 0.010"$) - NO CONING OF HOLES
BENDS ARE $\pm 1/2$ DEGREE
ALL OTHER MACHINING ($\pm 0.030"$)
ALL OTHER ASSEMBLY ($\pm 0.060"$)

DESCRIPTION	THREE SECTORS HEAVY WLL FRAME AND MONOPOLE ATTACHMENT HARDWARE WITH FIVE MOUNTING PIPES
CPD NO.	CEK 10/26/2018
DRAWN BY	CUSTOMER
ENG. APPROVAL	BMC 10/29/2018
PART NO.	VFA12-M3-WLL
DWG. NO.	VFA12-M3-WLL




NOTE:
OTHER SECTORS REMOVED FOR CLARITY.



TOLERANCE NOTES
TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE:
SAWED, SHEARED AND GAS CUT EDGES ($\pm 0.030"$)
DRILLED AND GAS CUT HOLES ($\pm 0.030"$) - NO CONING OF HOLES
LASER CUT EDGES AND HOLES ($\pm 0.010"$) - NO CONING OF HOLES
BENDS ARE $\pm 1/2$ DEGREE
ALL OTHER MACHINING ($\pm 0.030"$)
ALL OTHER ASSEMBLY ($\pm 0.060"$)

DESCRIPTION	THREE SECTORS HEAVY WLL FRAME AND MONOPOLE ATTACHMENT HARDWARE WITH FIVE MOUNTING PIPES
CPD NO.	CEK 10/26/2018
DRAWN BY	CUSTOMER
ENG. APPROVAL	BMC 10/29/2018
PART NO.	VFA12-M3-WLL
DWG. NO.	VFA12-M3-WLL





PARCEL ID: 360728140119
 ZONED: RESIDENTIAL NEIGHBORHOOD

PARCEL ID: 47662
 MAP & TAX LOT: 360728140121
 ZONED: RESIDENTIAL NEIGHBORHOOD

PREPARED FOR

AT&T
 NEW CINGULAR WIRELESS PCS,
 LLC ("AT&T")
 19801 SW 72ND AVE., STE. 200
 TUALATIN, OR 97062

Vendor:

J5 INFRASTRUCTURE
 PARTNERS

23 MAUCHLY #110
 IRVINE, CA 92618

J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
 928 STURM AVE
 WALLA WALLA, WA 99362
 PARCEL ID:
 47662 & 47722

DRAWN BY: RC

CHECKED BY: EVR

0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV DATE DESCRIPTION

Licensors:

Sheet Title:

UTILITY PLAN

Sheet Number:

E-1

NOTES:

- ALL WORK TO CONFORM TO N.E.C. LATEST STATE ADOPTED EDITION.
- LABEL SERVICE DISCONNECT WITH A RED TAG.
- SWITCH LEG CONDUCTORS SHALL BE THE SAME COLOR AS CIRCUIT CONDUCTORS.
- PULL ONE GROUND CONDUCTOR PER FLEXIBLE NONMETALLIC CONDUIT. FOR ALL OTHER CIRCUITS PULL A SEPARATE CONDUCTOR.
- ALL GFCI RECEPTACLES TO HAVE A DEDICATED GROUND WIRE.
- EQUIPMENT TERMINATION LUGS AND CONDUCTORS ARE RATED AT A MINIMUM OF 75°C.
- CONDUIT REQUIREMENTS
 - UNDERGROUND PVC (SCH 40 OR 80)
 - INDOOR: EMT (RGS IN TRAFFIC AREAS)
 - Outdoor (ABOVE GRADE): RGS

ABBREVIATIONS:

BCW	BARE COPPER WIRE
BTS	BASE TRANSCEIVER STATION
C	CONDUIT
(E)	EXISTING
EG	EQUIPMENT GROUND
(F)	FUTURE
FACP	FIRE ALARM CONTROL PANEL
GEN	GENERATOR
IG	ISOLATED GROUND
IMC	INTERMEDIATE METAL CONDUIT
LFMC	LIQUID TIGHT FLEXIBLE METAL CONDUIT
MCM	MILLION CIRCULAR MILLS
MI	MECHANICAL INTERLOCK
MP&S	SEE MECHANICAL PLANS & SPECIFICATIONS
(P)	PROPOSED
NEMA	NATIONAL ELECTRICAL MANUFACTURER'S ASSOCIATION
NL	NIGHT LIGHT - FIXTURE TO BE UNSWITCHED
PFB	PROVISION FOR FUTURE BREAKER
PVC	POLYVINYL CHLORIDE CONDUIT
(N)	RELOCATE
RG	RELAY TO MONITOR GENERATOR POWER
RU	RELAY TO MONITOR UTILITY POWER
TYP	TYPICAL
UON	UNLESS OTHERWISE NOTED
WP	WEATHERPROOF
GFCI	GROUND FAULT CIRCUIT INTERRUPTER

NOTE: SYMBOLS INDICATED ABOVE MAY NOT NECESSARILY APPEAR AS PART OF THESE DRAWINGS IF NOT REQUIRED.

VOLTAGE: 120/240V, 1 PHASE, 200A, 22 KAIC
 MAIN CB: 2P/200A
 BRANCH CB: TYPE 20


MOUNTING: SURFACE
 NEMA: 3R
 LOCATION: MOUNTED ON SHELTER EXTERIOR WALL

PANEL 'A'

VOLT AMPS		DESCRIPTION	POLE	BKR	CKT	A		B		DESCRIPTION	VOLT AMPS	
PHASE A	PHASE B					PHASE A	PHASE B	PHASE A	PHASE B			
1200	1200	RECTIFIER 1	2	30	1	+	2	30	2	RECTIFIER 7	1200	1200
1200	1200	RECTIFIER 2	2	30	5	+	4	30	2	RECTIFIER 8	1200	1200
1200	1200	RECTIFIER 3	2	30	9	+	8	30	2	RECTIFIER 9	1200	1200
1200	1200	RECTIFIER 4	2	30	13	+	12	30	2	RECTIFIER 10	1200	1200
1200	1200	RECTIFIER 5	2	30	17	+	16	30	2	RECTIFIER 11	1200	1200
1200	1200	RECTIFIER 6	2	30	21	+	20	30	2	RECTIFIER 12	1200	1200
180		G.F.I.	1	20	25	+	24	15	1	G.F.I.	180	180
		SPACE			27	+	26			SPACE		
					29	+	28					
					31	+	30					
					33	+	32					
					35	+	34					
					37	+	36					
					39	+	38					
7380	7200										7380	7200

PHASE A = 14,760
 PHASE B = 14,400

CONNECTED LOAD = 29,160 VA
 CONNECTED AMPS = 121.5 A



- KEY NOTES:
- UTILITY CO. TO INSTALL (P) METER/MAIN, 120/240V, 1Ø, 200A.
 - VERTIV - 48 Vdc POWER SYSTEM.
 - EXTERNAL DC CIRCUIT BREAKER.
 - 1" C - CAT5 CABLE 12 PAIR 24 AWG W/ DRAIN. REFER TO EQUIP. SPECS FOR DETAILS.
 - (2) 2" C - 2 250 KCMIL + 1 #2 GND RHW (FOR EACH CONDUIT).
 - 52 Vdc, 20 KW DC GENERATOR FURNISHED W/ FUSE PROTECTION.

2 AC PANEL SCHEDULE
 N.T.S.

1 SINGLE-LINE DIAGRAM (SLD)
 N.T.S.

PREPARED FOR

NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
 19801 SW 72ND AVE., STE. 200
 TUALATIN, OR 97062

Vendor:

23 MAUCHLY #110
 IRVINE, CA 92618

J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
 928 STURM AVE
 WALLA WALLA, WA 99362
 PARCEL ID:
 47662 & 47722

DRAWN BY: RC
 CHECKED BY: EVR

REV	DATE	DESCRIPTION
0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV DATE DESCRIPTION

Licensor:

Sheet Title:
ELECTRICAL PANEL SCHEDULE & SLDG


Sheet Number:
E-2

GROUNDING NOTES:

1. ALL DETAILS ARE SHOWN IN GENERAL TERMS. ACTUAL GROUNDING INSTALLATION REQUIREMENTS AND CONSTRUCTION ACCORDING TO SITE CONDITIONS.
2. ALL GROUNDING CONDUCTORS: #2 AWG SOLID BARE TINNED COPPER WIRE UNLESS OTHERWISE NOTED.
3. GROUND BAR LOCATED IN BASE OF EQUIPMENT WILL BE PROVIDED, FURNISHED AND INSTALLED BY THE VENDOR.
4. ALL BELOW GRADE CONNECTIONS: EXOTHERMIC WELD TYPE, ABOVE GRADE CONNECTIONS: EXOTHERMIC WELD TYPE.
5. GROUND RING SHALL BE LOCATED A MINIMUM OF 24" BELOW GRADE OR 6" MINIMUM BELOW THE FROST LINE.
6. INSTALL GROUND CONDUCTORS AND GROUND ROD MINIMUM OF 1'-0" FROM EQUIPMENT CONCRETE SLAB, SPREAD FOOTING, OR FENCE.
7. EXOTHERMIC WELD GROUND CONNECTION TO FENCE POST: TREAT WITH A COLD GALVANIZED SPRAY.
8. GROUND BARS:
 - A) EQUIPMENT GROUND BUS BAR (EGB) LOCATED AT THE BOTTOM OF ANTENNA POLE/MAST FOR MAKING GROUNDING JUMPER CONNECTIONS TO COAX FEEDER CABLES SHALL BE FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR. JUMPERS (FURNISHED BY OWNERS) SHALL BE INSTALLED AND CONNECTED BY ELECTRICAL CONTRACTOR.
9. ALL GROUNDING INSTALLATIONS AND CONNECTIONS SHALL BE MADE BY ELECTRICAL CONTRACTOR.
10. OBSERVE N.E.C. AND LOCAL UTILITY REQUIREMENTS FOR ELECTRICAL SERVICE GROUNDING.
11. GROUNDING ATTACHMENT TO TOWER SHALL BE AS PER MANUFACTURER'S RECOMMENDATIONS OR AT GROUNDING POINTS PROVIDED (2 MINIMUM).
12. IF EQUIPMENT IS IN A C.L. FENCE ENCLOSURE, GROUND ONLY CORNER POSTS AND SUPPORT POSTS OF GATE. IF CHAIN LINK LID IS USED, THEN GROUND LID ALSO.
13. GROUNDING AT PPC CABINET SHALL BE VERTICALLY INSTALLED.
14. ALL GROUNDING FOR ANTENNAS SHALL BE CONNECTED SO THAT IT WILL BY-PASS MAIN BUSS BAR.
15. ALL EMT RUNS SHALL BE GROUNDED AND HAVE A BUSHING, NO PVC ABOVE GROUND.
16. USE SEPARATE HOLES FOR GROUNDING AT BUSS BAR. NO "DOUBLE-UP" OF LUGS.
17. POWER AND TELCO CABINETS SHALL BE GROUNDED (BONDED) TOGETHER.
18. NO LB'S ALLOWED ON GROUNDING.
19. PROVIDE STAINLESS STEEL CLAMP AND BRASS TAGS ON COAX AT ANTENNAS AND DOGHOUSE.
20. ALL ELECTRICAL AND GROUNDING AT THE CELL SITE SHALL COMPLY WITH THE NATIONAL ELECTRICAL CODE (NEC), NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 780 (LATEST EDITION), AND MANUFACTURER SPECIFICATION.
21. IF THE AC PANEL IN THE POWER CABINET IS WIRED AS SERVICE ENTRANCE, THE AC SERVICE GROUND CONDUCTOR SHALL BE CONNECTED TO GROUND ELECTRODE SYSTEM. WHEN THE AC PANEL IN THE POWER CABINET IS CONSIDERED A SUB-PANEL, THE GROUND WIRE SHALL BE INSTALLED IN THE AC POWER CONDUIT. THE INSTALLATION SHALL BE PER LOCAL AND NATIONAL ELECTRIC CODE (NFPA-70).
22. EXOTHERMIC WELDING IS RECOMMENDED FOR GROUNDING CONNECTION WHERE PRACTICAL. OTHERWISE, THE CONNECTION SHALL BE MADE USING COMPRESSION TYPE-2 HOLES. LONG BARREL LUGS OR DOUBLE CRIMP CLAMP "C" CLAMP. THE COPPER CABLES SHALL BE COATED WITH ANTIOXIDANT (COPPER SHIELD) BEFORE MAKING THE CONNECTIONS. THE MANUFACTURER'S TORQUING RECOMMENDATIONS ON THE BOLT ASSEMBLY TO SECURE CONNECTIONS SHALL BE FOLLOWED.
23. THE ANTENNA CABLES SHALL BE GROUNDED AT THE TOP AND BOTTOM OF THE VERTICAL RUN FOR LIGHTING PROTECTION. THE ANTENNA CABLE SHIELD SHALL BE BONDED TO A COPPER GROUND BUSS AT THE LOWER MOST POINT OF A VERTICAL RUN JUST BEFORE IT BEGINS TO BEND TOWARD THE HORIZONTAL PLANE. WIRE RUNS TO GROUND SHALL BE KEPT AS STRAIGHT AND SHORT AS POSSIBLE. ANTENNA CABLE SHIELD SHALL BE GROUNDED JUST BEFORE ENTERING THE CELL CABINET. ANY ANTENNA CABLES OVER 200 FEET IN LENGTH SHALL ALSO BE EQUIPPED WITH ADDITIONAL GROUNDING AT MID-POINT.

24. ALL GROUNDING CONDUCTORS INSIDE THE BUILDING SHALL BE RUN IN CONDUIT RACEWAY SYSTEM, AND SHALL BE INSTALLED AS STRAIGHT AS PRACTICAL WITH MINOR BENDS TO AVOID OBSTRUCTIONS. THE BENDING RADIUS OF ANY #2 GROUNDING CONDUCTOR IS 8". PVC RACEWAY MAY BE FLEXIBLE OR RIGID PER THE FIELD CONDITIONS. GROUNDING CONDUCTORS SHALL NOT MAKE CONTACT WITH ANY METALLIC CONDUITS, SURFACES OR EQUIPMENT.
25. PROVIDE PVC SLEEVES WHERE GROUNDING CONDUCTORS PASS THROUGH THE BUILDING WALLS AND /OR CEILINGS.
26. INSTALL GROUND BUSHINGS ON ALL METALLIC CONDUITS AND BOND TO THE EQUIPMENT GROUND BUSS IN THE PANEL BOARD.
27. GROUND ANTENNA BASES, FRAMES, CABLE RACKS AND OTHER METALLIC COMPONENTS WITH #2 GROUNDING CONDUCTORS AND CONNECT TO INSULATED SURFACE MOUNTED GROUND BARS. CONNECTION DETAILS SHALL FOLLOW MANUFACTURER'S SPECIFICATIONS FOR GROUNDING.
28. ALL PROPOSED GROUNDING CONDUCTORS SHALL BE ROUTED AND CONNECTED TO THE MAIN GROUND BAR OR EXISTING GROUND RING.

3 GROUNDING NOTES
N.T.S.



NOTES:
1. GROUND BAR LOCATION IS SCHEMATIC AS SHOWN ON THIS SHEET AND ACTUAL LOCATION OF INSTALLATION WILL BE DETERMINED BY THE INSTALLER.
2. REFER TO ANTENNA PLAN FOR EXACT NUMBER OF ANTENNA, RRU AND DC SURGE SUPPRESSOR

4 TYP. ANTENNA GROUNDING DIAGRAM

1 NOT USED

2 NOT USED

PREPARED FOR



NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
19801 SW 72ND AVE., STE. 200
TUALATIN, OR 97062

Vendor:



23 MAUCHLY #110
IRVINE, CA 92618

J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
928 STURM AVE
WALLA WALLA, WA 99362
PARCEL ID:
47662 & 47722

DRAWN BY: RC

CHECKED BY: EVR

REV	DATE	DESCRIPTION
0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV DATE DESCRIPTION

Licenser:

Sheet Title:


GROUNDING NOTES

Sheet Number:

G-1

KEY NOTES:

- ① (P) AWG 2 BCW GROUND RING BURIED 30" BELOW GRADE.
- ② (P) EQUIP. GROUND BAR.
- ③ (P) AWG 2 BCW.
- ④ (P) GROUND TEST WELL.
- ⑤ (P) GROUND ROD.
- ⑥ ISOLATED GROUND ROD.
- ⑦ (P) ANTENNA GROUND BAR AT BOTTOM OF POLE.
- ⑧ (P) AWG 2 INSULATED COPPER GROUND TO EQUIP. GROUND BAR.




(P) FENCE POST, TYP.

GROUNDING LEGEND

- CADWELD CONNECTION (EXOTHERMIC WELD)
- MECHANICAL CONNECTION
- ⊗ GROUND ROD

KEY NOTES:

- ① ANTENNA GROUND BAR AT EACH SECTOR.
- ② AWG 2 INSULATED COPPER GROUND FROM (P) RRH AND DC9.
- ③ AWG 6 INSULATED COPPER GROUND WIRE FROM ANTENNA GROUND KIT TO ANTENNA GROUND BAR.
- ④ AWG 2 INSULATED COPPER GROUND TO ANTENNA GROUND BAR AT BOTTOM OF POLE



GROUNDING LEGEND

- CADWELD CONNECTION (EXOTHERMIC WELD)
- MECHANICAL CONNECTION
- ⊗ GROUND ROD

ANTENNA GROUNDING PLAN (TYP. PER SECTOR)


24"x36" SCALE: 3/8" = 1'-0"

KEY NOTES:

- ① AWG 2 INSULATED COPPER GROUND (HALO GROUND) (NOTE).
- ② AWG 2 BCW GROUND RING, BURIED 30" BELOW GRADE.
- ③ AWG 2 INSULATED COPPER GROUND.
- ④ AWG 2 BCW.
- ⑤ GROUND ROD.
- ⑥ GROUND TEST WELL.

NOTE:

HALO GROUND TO BE PROVIDED AND INSTALLED BY WIC MANUFACTURER.



(P) PRE-INSTALLED GROUND BAR

GROUNDING LEGEND

- CADWELD CONNECTION (EXOTHERMIC WELD)
- MECHANICAL CONNECTION
- ⊗ GROUND ROD

PREPARED FOR



NEW CINGULAR WIRELESS PCS, LLC ("AT&T")
19801 SW 72ND AVE., STE. 200
TUALATIN, OR 97062

Vendor:



23 MAUCHLY #110
IRVINE, CA 92618

J5 PROJECT ID: P-042954

Issued For:

WL4557
WALLA WALLA
MILL CREEK
928 STURM AVE
WALLA WALLA, WA 99362
PARCEL ID:
47662 & 47722

DRAWN BY: RC

CHECKED BY: EVR

0	4/4/23	100% CD
1	4/5/23	100% CD
2	4/20/23	100% CD
3	7/24/23	100% CD

REV	DATE	DESCRIPTION
-----	------	-------------

Licensor:

Sheet Title:

GROUNDING PLANS

Sheet Number:

G-2

